

# Big Data for Design Options Repository: Towards a DFMA Approach for Offsite Construction

## Abstract

A persistent barrier to the adoption of offsite construction is the lack of information for assessing prefabrication alternatives and the choices of suppliers. This study integrates three aspects of offsite construction, including BIM, DFMA and big data, to propose a Big data Design Options Repository (BIG-DOR). The proposed BIG-DOR system will connect BIM clients to manufacturers/supplier's information such as prefab component cost and production lead times. In this study, we propose a framework for integrating BIG-DOR into the process of offsite construction delivery. The design of the BIG-DOR system architecture, as well as the key components such as the DFMA option-based 3D objects classifier, is presented. The contribution to the knowledge of this study is the successful integration of BIM, big data, DFMA and offsite construction in a single framework and the development of a design alternatives assessment system for offsite construction adoption using this framework.

**Keywords:** Offsite construction, big data, DFMA, BIM, Big-DOR

## 1 Introduction

Although, the global construction market is expanding and forecasts show that it will grow by over 70% by 2025 and contribute up to 14.7% of global economic output by 2030, but the industry has remained unremarkable for poor productivity with only 1% growth over the last 20 years [1]. As identified in the UK government construction strategy, an estimated productivity savings of about £1.7 billion is targeted by 2020 through the adoption of modern approaches, digital technologies and the pervasive use of big data in the Architecture, Engineering, Construction and Operations (AECO) industry [2]. Conventionally, the AECO industry is significantly less productive than the manufacturing industry because of the complexities in construction operations, which generates enormous volumes of disparate data [3]. Big data is generated throughout the various phases of construction such as design, scheduling, costing, resources planning, logistics, construction, and facilities management; and occurs in various formats such as DWG (short for drawing), DXF (drawing exchange format), DGN (short for design), RVT (short for Revit), ifcXML (Industry Foundation Classes XML), ifcOWL (Industry Foundation ClassesOWL), DOC/XLS/PPT (Microsoft format), RM/MPG (video format), and JPEG (image format) [4]. Despite the availability of the big data sources in the AECO industry, the use of big data for design optimisation and construction process planning is inefficient, and this problem results from the disparate nature of construction processes [5].

The enduring challenge of low productivity and inefficient use of big data in construction has necessitated the adoption of manufacturing approaches such as offsite construction [3]. However, with offsite construction contributing only 7% to the UK construction market, the reluctance of construction investors against offsite construction has been linked to the lack of adequate information to evaluate the potential benefits and constraints of using offsite construction [6]. There is a mutually causal relationship between “low uptake of offsite construction” and the “inefficient use of big data” [7]. While the AECO industry has lagged in the efficient use of the big data for transforming and standardising construction processes, there have been improvements over the years through the implementation of frameworks such as Building

39 Information Modelling (BIM) [8, 9]. BIM has helped to improve building designs through efficient 3D  
40 visualisations, clash detection and collaborative planning [10]. BIM has also helped to enhance the  
41 collaborative approach for industry professionals to populate an nD federated model, where n denotes the  
42 levels and types of information such as geometry (3D), schedule (4D) and cost (5D) [11].

43 Despite the positive impacts of BIM on traditional construction approaches, there has been no proportionate  
44 positive impact of BIM adoption on offsite construction adoption [2]. While there are attempts to further  
45 improve the adoption of BIM-driven offsite construction through the introduction of Design for  
46 Manufacturing and Assembly (DFMA), there has been a little positive impact due to the lack of relevant  
47 information during design consideration for offsite construction. DFMA is an approach, which originated  
48 in the manufacturing industry, for evaluating and improving product design for optimal manufacturing and  
49 assembly [12]. The adoption of DFMA principles in the construction industry allows a designer to enhance  
50 the buildability of construction products through early-stage design consideration [13]. During early-stage  
51 design consideration, the client needs to consider various options of adopting offsite construction with  
52 regards to available prefabricated products, ease and cost of manufacture and supply as well as supply chain  
53 capabilities. At the point of the early-stage design, the design manager and client/owner must consider the  
54 appropriateness of offsite design options to ensure pricing accuracy, significant risk mitigation, more  
55 straightforward contracts and better payment arrangement with supply chain [14]. Currently, the  
56 combination of BIM and DFMA helps in consideration of alternatives for offsite construction. However,  
57 there is a limitation of access to vital information to answer questions such as the 'manufacturability of BIM  
58 design components', 'availability of existing off-shelf prefab components' and the 'capability of  
59 manufacturers/supplier' to deliver bespoke designs [15]. There remains a significant impediment to the  
60 adoption of offsite construction, which is caused by the lack of semantic homogeneity between BIM design  
61 authoring tools and manufacturer-based Product Information Models (PIM)/big data sources for DFMA  
62 implementation [5].

63 Existing platforms such as NBS National BIM Library, MODLAR and Revitcity provide data integration  
64 capabilities for designers, specifiers and manufacturers by hosting thousands of downloadable BIM objects  
65 from prefab manufacturers. However, these platforms do not provide the necessary big data engineering  
66 characteristics that are necessary for offsite alternatives analytics. DFMA in construction involves the  
67 massive design iterations, alternative BIM objects combinatorial optimisation for efficient offsite  
68 construction. Design options in BIM are the vast number of possible choices, including the configuration  
69 of building elements, geometry (shapes and sizes), and materials of design parts and component. The  
70 consideration of offsite construction during early-stage design involves the assessment of design options  
71 through the implementation of DFMA. DFMA is an iterative process of specifying the building components  
72 for prefabrication and onsite installation, which involves the assessment of design options with decision  
73 variables such as cost, availability of materials, ease of manufacture and assembly. The current gap of  
74 DFMA implementation in the construction industry is the lack of information for decision-making and the  
75 fact that suppliers often contribute too little during the early-stage design [16].


76 The ideal case and purpose of this study entail the integration of suppliers' databases and information  
77 sources during early-stage design consideration for the adoption of offsite construction [5]. The argument  
78 here is that the information required for the assessment of design options should come from the suppliers  
79 of such prefabricated products, which brings up the question, how can the disjointed databases of suppliers  
80 be integrated using a big data framework for the assessment of design options through DFMA for offsite

81 construction? This study aims to answer this question by proposing a Big Data Design Options Repository  
82 (Big-DOR) that: (i) enables the assessment of building design options through 3D BIM object classification  
83 (ii) provides access to suppliers-based information for prefabricated products through a big data framework  
84 (iii) supports optimal DFMA through BIM-based big data integration. In this study, we presented a  
85 background on the main components, including BIM, DFMA and big data, which will facilitate easy  
86 adoption of offsite construction. Abandah et al. [17] reported an argument that the most significant growth  
87 in construction productivity will be realised from the implementation of automated offsite activities that are  
88 facilitated by BIM. Offsite construction is preferable to traditional construction due to improved quality,  
89 more stable working conditions, standardised materials and processes, good health and safety, lower cost  
90 and reduced labour [18,19, 20]. The proposed Big-DOR system is expected to help in increasing the  
91 adoption of offsite construction by enabling the optimal selection of prefabricated materials and  
92 appointment of suppliers. Furthermore, in this study, we developed and tested a framework that details the  
93 system architecture and the critical components of a Big Data Design Options Repository (Big-DOR).

## 94 **2 Background**

95 This study approaches the duo problem of “low adoption of offsite construction” and “poor usage of big  
96 data” in construction through the integration of big data with other vital aspects of offsite construction such  
97 as BIM and DFMA for informed decision-making and optimisation [4, 5]. On the one hand, DFMA is  
98 considered as an approach that facilitates optimisation of offsite construction from the design phase and  
99 can be achieved more efficiently through BIM adoption [12, 21, 22]. On the other hand, BIM is an important  
100 technology that has demonstrated remarkable positive impacts and benefits on construction activities but  
101 continues to be limited by lack of adequate data during design considerations [17].

102 The changing markets have pushed the construction industry to gradually start adopting manufacturing  
103 approaches such as offsite construction [23, 24]. The adoption of offsite construction comes with benefits  
104 such as faster project delivery, greater consistency and quality, lower costs, lesser sites disruptions, and  
105 increased jobs stability for workers [25]. However, the first five barriers to the adoption of offsite  
106 construction include the enormous capital cost, the difficulty of achieving economy of scale, the complex  
107 interfacing between systems, the nature of planning systems and the inability to freeze designs early-on.  
108 Liu et al. [26] also identified some possible disadvantages of offsite prefabrication. They include: (1) the  
109 need for components installation expertise to guarantee structural integrity; (2) transportation and hoisting  
110 cost of large-scale prefabricated components; (3) the low flexibility of responding to change in construction  
111 demand, and; (4) the need for large-scale mechanical equipment.



*Figure 1: Aspects of offsite construction in relation to Big-DOR*

112  
113

114 In Figure 1, it is clear that BIM has a direct impact on improving the adoption of offsite construction by  
 115 enabling the simulation of the entire offsite construction project in a virtual environment, and facilitating  
 116 the automation of some processes of construction [8, 27]. BIM has been proven over the years to mitigate  
 117 some of the barriers to the adoption of offsite construction, and it offers even more benefits such as better  
 118 designs, faster delivery processes, better quality, lifecycle data, better team management, minimisation of  
 119 costs and reduction of design changes due to unforeseen site conditions [28, 29]. However contrary to the  
 120 case of traditional construction, BIM implementation alone is not enough to tackle most of the critical  
 121 barriers to the adoption of offsite construction such as lack of certainty at the early design stage and the  
 122 difficulty of achieving economy of scale [30, 26]. It is common to find the integration of DFMA and BIM  
 123 in attempts to achieve better planning for offsite construction, DFMA helps to achieve better economy of  
 124 scale, reduced order lead time and increased feasibility for products maintenance and component  
 125 replacement [31]. DFMA also enables concurrent engineering, Just-In-Time (JIT) supply, waste  
 126 minimisation and cleaner work environments [32].

127 The implementation of DFMA through BIM for supporting offsite construction is negatively affected by  
 128 the lack of access to necessary information or data for assessing design options [16]. Existing platforms  
 129 such as BIMobjects, NBS library and Revit City allow the upload of BIM objects/manufacturers' PIM for  
 130 design integration [17]. As expected, this is beginning to encourage faster adoption of prefabrication as it  
 131 allows manufacturers' products to get specified in BIM. However, in the case of assessing or comparing the  
 132 available choices of prefab products for the adoption of offsite construction, it becomes incredibly tedious  
 133 and almost impossible for a designer to download all potential products.

134 Considering the vast number of BIM design options, a big data framework is required to provide the  
 135 necessary information required to enable a DFMA-based assessment [6]. The proposed Big-DOR system

136 will mitigate the barriers of high capital costs, lack of certainty of cost and delivery time by allowing  
137 unlimited data flow between suppliers and designers. The proposed Big-DOR system will also be the  
138 missing link between big data and DFMA, and provide access for the necessary information to support  
139 DFMA. The Big-DOR system will rely on a big data framework acquiring, processing, analysing and  
140 applying data from existing disjointed databases of prefab suppliers to provide the necessary information  
141 required for assessing DFMA design options. The data sourced by the Big-DOR systems fits the definition  
142 of big data in terms of volume, velocity, variety and veracity. Therefore, a big data engineering approach  
143 will enable access to existing distributed databases. This section provides a review of extant literature in  
144 the domain of offsite construction optimisation from the perspectives of BIM, DFMA and big data.

## 145 **2.1 BIM and Offsite Construction**

146 With the argument thus far, evidence from literature further supports the assertion that offsite construction  
147 offers advantages such as better quality, higher whole-life value, lower costs, higher productivity and  
148 speedy delivery of construction projects [33, 34, 35]. However, the adoption of offsite construction comes  
149 with some barriers and constraints such as high initial costs, longer lead times due to pre-planning,  
150 unfavourable past experiences of collapse of the 1960s, lack of knowledge of the benefits, lack of codes  
151 and standards and poor integration of supply chain [36, 37, 38].

152 Abanda et al. [17] reviewed the literature on how BIM can enhance the benefits and also mitigate the  
153 barriers of offsite construction. While traditional construction often involves high wastage of materials  
154 during onsite processing as compared with offsite construction, BIM can enable a collaborative and yet  
155 remote design for offsite construction [39]. Through BIM adoption for offsite construction, inefficient and  
156 unnecessary onsite activities can be replaced by virtual BIM coordination for development and testing of  
157 building components at remote factories [40]. Offsite construction improves productivity by enabling  
158 concurrent production, which can be enhanced by BIM-enabled collaboration among stakeholders to  
159 effectively manage cost, fast-track the delivery of projects, avoid clashes, and eliminate wastes [8, 41]. A  
160 future opportunity identified by Kim et al. [42], entails the use of cloud BIM-based data exchange for the  
161 management of activities across multiple stakeholders in dispersed workstations.

162 BIM integration will further revolutionise the design process for such construction in the areas of generating  
163 automated detailed shop drawings for prefab components from 3D models as against the traditional  
164 approach of drawing sections and views from 2D plans [17]. The present-day challenge is to enable the  
165 integration of BIM for the coordination of supply chain activities to integrate the decision of suppliers and  
166 identify the existing interdependencies to minimise the total material management cost [43]. With the  
167 potential of offsite construction to improve the economic, environmental and social sustainability of the  
168 construction industry, it is essential to integrate BIM to achieve these potentials [44]. Summarily, BIM-  
169 enabled offsite construction is essential for collaboration, compliance checking, knowledge sharing, clash  
170 detection, and design optimisation.

## 171 **2.2 Offsite Construction and DFMA Optimisation**

172 In the adoption of offsite construction, the concept of DFMA is essential for evaluating the building design  
173 to improve the process of manufacturing, handling and onsite assembly [12]. The benefits of adopting  
174 DFMA are evident from its mandatory implementation on Singapore government land development

175 projects, which has driven the number of offsite construction projects from less than 10 in 2013 to about 60  
176 in 2018 [13]. The adoption of DFMA in construction will drive the desired goal for standardised  
177 construction processes, increased use of prefabricated components and ultimately, the adoption of offsite  
178 construction [45]. However, the adoption of DFMA in the construction industry has not been encouraging  
179 with about only 7% of construction projects in the UK using offsite construction approaches [6]. Gao et al.  
180 [13] identified a number of factors that affect the uptake of offsite construction, they include: project-  
181 specific factors like site constraints, transportation considerations, BIM and DFMA adoption. Goulding et  
182 al. [46] considered offsite construction as a complex process, which requires the integration of DFMA into  
183 the design. Gbadamosi et al. [5] also identified the “complexity of offsite construction” and the “wide  
184 variety of data formats in the construction industry” as significant motivations for the integration of DFMA  
185 in the adoption of offsite construction.

186 In the construction industry, DFMA involves the development of suitable designs for a chosen construction  
187 method to ensure optimal use of resources. There are many possible objectives for DFMA optimisation,  
188 which must be considered during design [16]. The primary objectives include cost, schedule, and quality  
189 while other relevant objectives include standardisation, part minimisation, preassembly engineering,  
190 installation review, sustainability, health and safety, and quality management [47, 48]. Although the  
191 adoption of DFMA for offsite construction optimisation is still nascent in the construction industry, there  
192 are some literature that explored the adoption of DFMA for offsite construction optimisation. Martinez et  
193 al. [49] adopted the principles of DFMA, lean manufacturing, and expert knowledge to develop a flexible  
194 field factory, which ensures flexible and mobile manufacture and assembly of precast components. The  
195 principles of DFMA have been adopted as the basis of a suitability assessment criteria for a standardised  
196 bridge construction using precast components [50]. Yuan et al. [21] integrated the principles of DFMA for  
197 the parametric design of prefabricated components in offsite construction. Gbadamosi et al. [5] also  
198 combined the principles of DFMA with lean construction for developing a BIM-based optimiser for onsite  
199 assembly of prefabricated components. With evidence from literature, parametric modelling is an essential  
200 aspect of adopting DFMA principles for offsite construction.

## 201 **2.3 BIM and DFMA**

202 BIM is a real opportunity in the AECO industry for enabling efficient construction planning through  
203 parametric modelling and information sharing [29]. BIM has enabled the capability of construction  
204 stakeholders such as clients, designers and facility managers to collect, store and reuse project information  
205 [51]. The benefits of BIM in creating an efficient working approach among construction professionals have  
206 been proven by the wide adoption of 3D BIM by architects and engineers for design visualisation and  
207 evaluation of design options [52]. Construction planners and quantity surveyors have also adopted 4D and  
208 5D BIM for construction activities scheduling and project cost estimating respectively.

209 Some studies have integrated the principles of DFMA with BIM because of the capability of BIM for object-  
210 based parametric modelling and integrated design information [5, 21, 53]. Abandah et al. [54] identified  
211 some drivers of BIM usage for integrating principles that improve construction efficiency. These drivers  
212 include: (1) existing BIM authoring and management software (e.g Revit, ArchiCAD, Navisworks,  
213 AutodeskQTO, ConstructSim, Bentley, EnergyPlus); (2) existing data in BIM components libraries (e.g  
214 BIMObject, SmartBIM, NBS Library and Object depository) and; (3) robust interoperability standards (e.g  
215 syntactic, technical, semantic and organisational interoperability). Despite the existence of these drivers,

216 BIM implementation is still mostly limited to parametric modelling, while the integration of DFMA is still  
217 below par due to the unavailability of adequate data and poorly harnessed big data.

## 218 **2.4 Offsite construction and Big Data**

219 So far, a significant gap in knowledge is the lack of efficient ways to seamlessly capture, store and utilise  
220 data for adopting offsite construction. Existing big data processing and storage techniques have been  
221 explored big data engineering techniques for improving construction operations. An example is the use of  
222 Map Reduce (MR) for optimal retrieval of BIM data (MR4B) [55]. A big data BIM platform in a distributed  
223 framework called BIMCloud have utilised big data storage systems such as Apache Cassandra [56]. Big  
224 data analytics techniques have also been adopted to optimise various aspects of construction [4]. Machine  
225 Learning (ML) techniques including rule-based approaches, artificial neural networks and case-based  
226 reasoning methods have been used in construction aspects such as automated compliance checking,  
227 construction document classification, optimal resource assignment and fault detection [57,58, 59, 60].

228 Although, some literature exists on the integration of DFMA with BIM for offsite construction, however,  
229 there remains no research that has developed any real-world application of big data-driven DFMA  
230 integration with BIM to enhance the adoption of offsite construction [5]. The lack of comprehensive data  
231 to assess the various DFMA options as well as the cost and time implications of adopting alternative designs  
232 remains a significant barrier to the adoption of offsite construction [61]. An exhaustive rationale for the  
233 integration of big data to drive the adoption of offsite construction is considered from the perspectives of  
234 BIM adoption and the changing data trends due to offsite implementation. Bilal et al. [4] noted that  
235 construction data is voluminous, heterogeneous and dynamic and if properly harnessed, can be used to  
236 optimise construction operations.

### 237 **2.4.1 Big data for BIM-based DFMA**

238 At the design stage for offsite construction, DFMA increases data requirements for product simplification,  
239 process planning, costing, scheduling, and optimisation [62]. Furthermore, DFMA can also generate  
240 voluminous data for production analysis, logistics planning, and assembly sequencing. Also, DFMA  
241 requires the integration of important information such as resource capabilities, key performance indicators  
242 and so on. Summarily, big data application is required for BIM-based DFMA design to ensure that the  
243 design of components is in congruence with manufacturer capabilities and can be mass-produced with  
244 competitive pricing, economy of scale and efficient logistics.

245 Another aspect of BIM-based big data requirement for DFMA is structural considerations where factors  
246 such as the weight of materials, structural strength, hoisting and lifting requirements and the requirement  
247 for temporary support will be considered when developing the detailed design. Big data application is also  
248 required to enable the structural analysis of a federated BIM model as well as the structural-effect analysis  
249 of individual components of the model. The design of prefabricated components, modules or units should  
250 include the considerations of their position, orientation, and accessibility for installation and maintenance.  
251 Likewise, there is a higher requirement for big data and information, which is attributable to the level of  
252 adoption of offsite construction. Li et al. [63] highlighted a hierarchical classification of prefabrication  
253 products, which includes: (i) construction materials such as concrete and glass; (ii) components such as  
254 staircase and partition wall; (iii) modules such as bathroom pod and building façade, and volumetric units.

255 Table 1 shows a description of various levels of Offsite Construction Adoption (OCA) and some  
 256 corresponding BIM information requirement.

257 *Table 1: 3D BIM Information Requirement for Existing Design Options for Offsite Construction*

ID	Existing Options	Description	BIM information requirement
OCA-0	Traditional construction	Involves the delivery of materials to site and construction activities mainly done on-site.	Shape, dimension, layout, material, quantity
OCA-1	Prefabricated components	Involves the prefabrication and installation of basic components such as staircase sections, partition wall, etc.	Shape, material, dimension, component specification, weight, volume, connection specification
OCA-2	Prefabricated modules	Involves the combined prefabrication of associated components (modules) such as 'wall section with fitted door and window' and the onsite installation	Shape, size, structure loads, weight, volume, material, the specification for coupling and decomposition
OCA-3	Prefabricated volumetric units	Involves the prefabrication volumetric units with some preinstalled components but requires some onsite finishes as well as installation.	Shape, dimension, weight, volume, material, the specification for coupling and decomposition, relationship between whole and parts, relationship between parent and child products
OCA-4	Prefabricated pre-finished volumetric units (PPVC)	Involves the prefabrication and pre-finishing of volumetric units which only require onsite installation	Shape, dimension, weight, volume, material, the specification for coupling and decomposition, relationship between whole and parts, relationship between parent and child products, key constraints

258 It is important to consider the flexibility to assess these offsite construction options based on factors such  
 259 as the client's existing capabilities, the feasibility of adopting new methods, resource availability, project  
 260 requirements, cost performance, schedule performance and whole-life value. A major limitation of the  
 261 flexibility of adopting these options is the rigidity of 3D BIM models, which are often constrained to a  
 262 specific OCA level. Usually, 3D models are prerequisites to work items scheduling (4D) and costing (5D),  
 263 which makes it presumably impractical to compare the 3D models of various OCA levels based on schedule  
 264 and cost efficiency while in the process of 3D design [54].

265 It is also important to consider the practicality of adopting offsite construction approaches by traditional  
 266 construction companies. Adopting offsite construction could have negative short-term effects on the profit  
 267 margin considering their peculiarities such as existing resources and processes [7]. Therefore, the need for  
 268 an optimisation approach through DFMA for adopting offsite construction is hinged on the ability to assess  
 269 various manufacturing options and the flexibility of transitioning from conventional approaches without  
 270 the traditional construction companies having to suddenly and completely discard its existing resources and  
 271 processes [2, 6].

### 272 **3 The Proposed Big Data Design Options Repository (Big-DOR)**

273 The benefits of BIM implementation have been mainly focused on traditional methods of construction while  
 274 BIM implementation for offsite construction optimisation is still deficient. This is due to the lack of  
 275 semantic connection between BIM information requirement for offsite construction and the big data sources  
 276 of such information [17, 21, 62, 64]. In this study, the following are the challenges: (i) enabling offsite  
 277 construction options- evaluation through BIM-model components categorisation; (ii) identifying big data  
 278 sources in offsite construction for assessing DFMA options; (iii) designing a DFMA options repository for



279 application of big data in offsite construction and; (iv) integration of DFMA options repository with BIM.  
280 This section presents a framework to solve these challenges through the following: (a) design rationale (b)  
281 system architecture and (c) the technical features of the main components, which include, big data  
282 mediation schema, Big Data Design Options Repository, BIM model integration, option-based object  
283 classifier and user interface.

### 284 **3.1 Design Rationale**


285 The most crucial focus of this study is to enable the optimisation of offsite construction choices using big  
286 data and BIM-based DFMA options classification. The Big-DOR is designed to bridge the gap between the  
287 existing BIM authoring tools and big data sources in offsite construction sources. This gap still exists  
288 because the currently available BIM objects are domain-specific and have been tailored to suit existing  
289 methods of construction rather than offsite construction. This gap is further widened because the accuracy  
290 of cost estimation of BIM models is also dependent on the model, and this makes it difficult to compare the  
291 cost of two BIM model options without designing both options. The DFMA option-based 3D object  
292 classifier is designed to bridge this gap by using various features and relationships of various DFMA options  
293 available. Furthermore, there are various sources of big data from offsite construction stakeholders who use  
294 domain-specific database schemas, which cannot be easily integrated with the existing schemas in the  
295 construction industry. To maximise the usage of available big data both within and outside the construction  
296 industry, big data schema mediation component is integrated with the Big-DOR to ensure usability and  
297 scalability of the system. The following are the objectives of this study, (i) develop BIM model 3D object  
298 classifier using geometric features and DFMA option component relationships, (ii) develop a big data  
299 schema mediation system using peer-to-peer schema integration structure, (iii) integrate big data from  
300 offsite construction sources using relational database management system and (iv) develop an application  
301 user interface for big data input, management, and visualisation.

### 302 **3.2 System Architecture**

303 The conceptual architecture of a Big-DOR system for big data integration in offsite construction using BIM-  
304 based DFMA is shown in Figure 1. The system will facilitate the usage of big data for optimising the DFMA  
305 using essential factors such as cost, productivity, and constraints. The Big-DOR system includes four main  
306 components within a four-layered big data architecture. They include:

- 307 1. Big-Data Storage Layer: This layer includes two big data sources including offsite construction  
308 suppliers, and BIM users;
- 309 2. Big-Data Processing Layer: This layer holds the DFMA options repository, which uses big data  
310 mediation schema to coordinate peer-to-peer database integration;
- 311 3. Big-Data Analytics Layer: This layer will contain the DFMA option-based 3D object classifier,  
312 which uses DFMA features and relationships to classify 3D BIM objects to various design options  
313 and support optimal decision making;
- 314 4. Big-Data Application Layer: This layer integrates the user interface with a BIM authoring tool to  
315 enable the assessment of BIM design models.

316 Full-scale development of the Big-DOR system will integrate big data from the various autonomous and  
317 heterogenous sources for optimising designs. The critical components of the system architecture are  
318 described subsequently.



319

320

*Figure 2: System Architecture for Big-DOR*

321 The proposed Big-DOR system is a web application that has the backend big data platform running on the  
 322 Amazon Web Services (AWS) for cloud storage on S3 bucket and supplier’s database query logic on  
 323 lambda. Existing Rest APIs for getting suppliers’ products information was considered for this study  
 324 including NBS library (<https://toolkit.thenbs.com/articles/for-software-developers>). The proposed Big-  
 325 DOR system will integrate existing big data platforms to enable access to suppliers’ product information  
 326 for design options assessment by BIM clients. The current proposed system architecture is for a standalone  
 327 web app, but in the future, the Big-DOR will be integrated into BIM authoring tools to enhance the ease of  
 328 use.

### 329 3.3 Big Data Sources


330 Big data is generated in various phases of construction such as design, scheduling, costing, resources  
 331 planning, logistics, construction, and facilities management, and occurs in various formats such as DWG  
 332 (short for drawing), DXF (drawing exchange format), DGN (short for design), RVT (short for Revit),  
 333 ifcXML (Industry Foundation Classes XML), ifcOWL (Industry Foundation ClassesOWL),  
 334 DOC/XLS/PPT (Microsoft format), RM/MPG (video format), and JPEG (image format). There are two  
 335 primary sources of big data input into the Big-DOR system, they include:

- 336 1. **BIM Authoring Tools:** These tools are usually used by designers to add building information,  
 337 which typically includes data about thousands of BIM objects with variants in terms of materials,  
 338 shapes and sizes. These objects are created, modified and reused within BIM authoring tools where  
 339 they can be classified during “quantity take-off” and used for cost estimation [65]. The quantity  
 340 take-off of objects from BIM models requires accurate object classification into “work packages”  
 341 or “prefabricated components” in offsite construction to enable synergy with data from other  
 342 sources such as unit cost and production constraints of prefabricated products [66].
- 343 2. **Suppliers’ Product Information Modelling (PIM) Tools:** Existing manufacturers information  
 344 platforms such as ‘NBS library’ and ‘BIMObject’ hosts above 1 million users with millions of BIM

345 object variants from various manufacturers. These platforms are designed to improve access to  
346 suppliers' product specification for BIM design integration. The challenge is to enable the  
347 comparative assessments of the vast number of prefab PIMs (or DFMA components) by multiple  
348 suppliers for BIM design optimisation. There are multiple objectives and project phases to consider  
349 during design optimisation, which makes design optimisation tedious, however, a major objective  
350 of the Big-DOR system is to map BIM objects to DFMA design options with relevant information  
351 obtained from suppliers/manufacturers data sources using a big data framework [67].

### 352 **3.4 DFMA Option-based 3D Object Classifier**

353 The function of this module, the DFMA option-based object classifier is to utilise a comprehensive DFMA  
354 knowledge system for classifying BIM objects into DFMA components according to the DFMA design  
355 options. Although, some object classification systems such as SeeBIM, have used a rule-based approach to  
356 integrate domain experts' knowledge for object classification [68]. Rule-based inference approaches have  
357 limited practical use for object classification in complicated design optimisation for offsite construction  
358 because it can be error-prone, the validity of rules can be challenging and, equally stringent rules can be  
359 conflicting [65]. The proposed approach of representing DFMA knowledge for the BIM object  
360 classification module is the use of a "Matrix System" to store the features and relationships, which will then  
361 be used for matching BIM objects with DFMA components. The workflow for continuously compiling a  
362 comprehensive DFMA knowledge matrix for classifying BIM objects into DFMA components is shown in  
363 Figure 3. It is important to note that a DFMA component can be formed either by aggregating or segregating  
364 BIM objects depending on the DFMA option. Also, DFMA components are defined in the comprehensive  
365 knowledge matrix using the features and relationship of its constituent objects.



366

367 **Figure 3:** Workflow for a continuous compilation of DFMA knowledge matrix for BIM object classification

368 Relevant features for BIM objects classification include shape, size, orientation, location, material, weight  
 369 volume and so on, while objects relationship includes level, grid, proximity, orthogonality and parallelism  
 370 and so on [69, 68, 65]. The compiled list of DFMA components for each design option is then computed  
 371 using the algorithm shown in Figure 4.

```

Algorithm
Input: 3D BIM Model ( $\psi$ ) and DFMA Strategies Repository ( $\phi$ )
Output: Optimal 5D BIM Model ( $\psi^*$ )
index Parameters ( $V_{kx}$ )

get components  $c_i$  from  $\psi$ 
get design options  $R_j$  from  $\phi$ 
  for each
    group  $c_i$  by  $R_j \forall$  work items for  $R_j = W_{n,i}$ 
      get  $W_{n,i}$ 
      for  $W_{n,i}$  do:
        get design KPIs  $K_x = \begin{cases} Kx.c \text{ if } Kx = \text{cost index} \\ Kx.d \text{ if } Kx = \text{duration index} \\ Kx.k \text{ if } Kx = \text{constraint index} \end{cases}$ 
        for each  $k$  in KPIs do:
          get values ( $V$ ) for  $V_{kx}$ 
          compute  $K_x$ 

    optim.type='ABC'
     $v' = \text{optim.solve}(V)$ 
     $m' = m * v'$ 
  return  $m'$ 
end
  
```

372

373 **Figure 4: Object Classification Algorithm**

374 The comprehensive knowledge base of DFMA components can be organised in matrix format using the  
 375 possible relationships between the constituent object types. In Table 2, a sample knowledge matrix where  
 376 the values “-1”, “0” and “1” are assigned for relationships that “never exist”, “may exist” and “always exist”  
 377 respectively between object types for a DFMA component. The sample knowledge matrix consists of three  
 378 object types X1, X2 and X3, and four relations.

379 **Table 2: An example of DFMA knowledge matrix**

	Relation 1	Relation 2	Relation 3	Relation 4
$X_1, X_1$	0	1	1	1
$X_1, X_2$	1	-1	-1	0
$X_1, X_3$	-1	0	0	0
$X_2, X_1$	1	0	1	1
$X_2, X_2$	0	-1	1	-1
$X_2, X_3$	1	1	0	0
$X_3, X_1$	1	1	0	-1
$X_3, X_2$	0	0	1	-1
$X_3, X_3$	1	0	0	1

380 Given a 3D BIM model with two objects B1 and B2, a BIM model fact matrix of the relationship between  
 381 the objects can be organised in the same matrix format as the sample DFMA knowledge matrix shown in

382 Table 2. While X1, X2, and X3 are object types in the knowledge matrix, B1 and B2 are actual objects in  
 383 the BIM model. Therefore, there are no such pairs as [B1, B1] as we have [X1, X1]. Also, there is no such  
 384 value as “0” in the fact matrix because the objects either have a relationship “1” or not “-1”. An example  
 385 of a BIM model fact matrix is shown in Table 3.

386 The similarity between the objects in the 3D BIM model and the object types of the DFMA components in  
 387 the comprehensive knowledge matrix can be found by computing the inner product of the vectors in each  
 388 row of the knowledge matrix and fact matrix.

389 *Table 3: A sample BIM model fact matrix.*

	Relation 1	Relation 2	Relation 3	Relation 4
B1, B2	-1	1	1	1
B2, B1	1	-1	-1	1


390 Let  $K(a, b)$  be the four-dimensional vector of each row in the knowledge matrix, where  $a, b \in [1, 2, 3, 4]$ ,  
 391 and  $F(x, y)$  be the four-dimensional vector of each row in the factual matrix, where  $x, y \in [1, 2]$ ,  $a \neq b$ . The  
 392 similarity values  $S(a, b)(x, y)$  of the 3D BIM objects and DFMA component object types are computed  
 393 using equation 1, below.

$$S(a, b)(x, y) = \frac{K(a, b) \cdot F(x, y)}{|K(a, b)| |F(x, y)|} \quad (1)$$

394 A semantic path can now be established between the objects that exist in any BIM model and the object  
 395 types that make up the prefabricated components for DFMA options in the knowledge matrix. The object  
 396 classifier can then output a list of prefabricated components that exist in a BIM model according to the  
 397 DFMA option for comparative assessment.

398 **3.5 Big Data Design Options Repository**

399 The primary function of the Big Data Design Options Repository is the facilitation of schema mediation  
 400 for semantic big data sharing between various data models such as the industry foundation classes  
 401 extensible markup language (ifcXML) and functionalities of the Big-DOR is to hold (i) the comprehensive  
 402 knowledge matrix for classifying BIM ifcObjects into prefabrication products (ii) offsite construction peers  
 403 mapping (iii) catalogue of standardised prefabrication products and; (iv) algorithm for semantic schema  
 404 matching and mapping. Figure 5 shows the peer-to-peer data integration for the Big-DOR. It illustrates a  
 405 peer-to-peer big-data integration system that enables offsite construction practitioners to access data for  
 406 assessing various options for DFMA.



407

408

*Figure 5: Peer big data integration setting for Big-DOR*

409

To enable big-data integration for offsite construction optimisation through the Big-DOR, it is essential to reconcile the heterogeneity of the big-data storage and schema of offsite construction peers. Given the vast number of Potential Offsite Construction peers  $POC_i$   $\{POC_1, \dots, POC_n\}$  and a set of Peer Schemas  $SOC_j$   $\{SOC_1, \dots, SOC_m\}$ , unlimited access to data from a set of stored relations  $T_{bdi}$  at each offsite construction peer  $POC_i$ , will be enabled to support the combinatorial optimisation of a set of objects  $C_{fci}$  in BIM models for identifying opportunities for optimal integration of prefabrication in designs. The standardised DFMA catalogue will enable the query routing for assessing the data in the stored relation  $DOCP$ , of the offsite construction peers. An example of the storage description of the standardised DFMA catalogue (SDC) is:

417

SDC:  $DFMA\_P\_cost(G\_ID, des\_cost..)$   $\subseteq$  Design-Based peer:  $DFMA\_P(G\_ID, des\_cost..)$

418

$\subseteq$  Manufacture-B peer:  $DFMA\_P(G\_ID, Prod\_cost..)$

419

$\subseteq$  Onsite\_A-B peer:  $DFMA\_P(G\_ID, Storage\_cost..)$

420

$\subseteq$  Logistics-B peer:  $DFMA\_P(G\_ID, Transp\_cost..)$

421

$\subseteq$  Management-B peer:  $DFMA\_P(G\_ID, renewal\_cost..)$

422

The standardised DFMA catalogue (SDC) also stores information about registered peers and allows user-

423


input to enable comparative assessment of peers based on past performance of the participating peers.

424

SDC:  $DFMA\_P\_cost(G\_ID, des\_cost..)$   $\subseteq$  D-B peer:  $ID(Peer\_ID, Peer\_type, Location, Experience)$

425 **4 Case study**

426 The proposed framework was applied to assess the DFMA strategies of a block of five-offices. The total  
427 floor area of the office block is 1200 ft<sup>2</sup> (111.48m<sup>2</sup>). The model was developed in Autodesk Revit and  
428 exported in FBX format to the proposed Big-DOR application. Important information for enabling  
429 automatic BIM objects classification was specified using Revit functionalities, as shown in Figure 6.




430

431 **Figure 6:** Specification of BIM Object Classification Features and Relationships in a Revit Environment


432 The purpose of this illustrative case study is to demonstrated the functionality of the Big-DOR system for  
433 the optimisation of offsite delivery method and the selection of offsite suppliers. This section presents the  
434 development of a decision optimisation algorithm that compares the suppliers' price quotation with the  
435 estimated whole-life value of the available methods. The FBX format of the BIM model was uploaded to  
436 the Big-DOR prototype and big data storage and analytics was implemented using Amazon Web Services  
437 (AWS) including Amazon S3 and Amazon Lambda. Figures 7 and 8 show the application user interface  
438 and the cloud service interface for the proposed Big-DOR system. A description of the illustrative case  
439 study is subsequently presented.





440  
441

Figure 7: Prototype Big-DOR Application



442

443 Figure 8: Cloud Storage of Classified BIM Objects on Amazon S3 in json Format

444 **4.1 Optimisation algorithm**

445 A typical offsite construction project consists of five phases viz design, manufacture, logistics/handling,  
 446 assembly, and facility management. The design phase entails critical evaluation of DFMA choices with a  
 447 vast number of decision variables for offsite construction choices. An overview of some critical design  
 448 consideration has been explained for the proposed framework. For this case study, the following four  
 449 objectives were set for comparing the DFMA strategies: (i) cost; (ii) duration; (iii) ease of implementation  
 450 (iv) whole-life value.

**Table 4:** Set of variables for proposed DFMA optimisation

	Notation for a set of variables	Set of variables	Notation for variables	Variables	Value range (Z)
<b>Design</b>	$\beta_{PF,Di}$	Design delivery efficiency factor	ER <sub>D</sub>	Designer DFMA expertise rating for	[0-2]
			EL <sub>D</sub>	Designer DFMA experience level	[0-4]
	$\phi_{PF}^{Di}$	Design constraints factor	C <sub>D</sub>	Design complexity	[0-4]
			DD <sub>WI</sub>	Work item detailing difficulty	[0-4]
$K_{Di}^{WI}$	Design unit cost for work item (i)	$\mu$ D	Average unit cost for work item design		
<b>Manufacture</b>	$\beta_{PF,Mi}$	Production efficiency factor	EX <sub>M</sub>	Manufacturing process experience for work item	[0-4]
			EM <sub>M</sub>	Experience of material use in production	[0-4]
			S <sub>PM</sub>	Part standardisation rating	[0-2]
	$\phi_{PF}^{Mi}$	Production constraints factor	SR <sub>M</sub>	Set up requirement	[0-2]
FP			Fragility of parts	[0-2]	
$K_{Mi}^{WI}$	Offsite production unit cost for work item (i)	$\mu$ M	Average unit cost for work item production	Value	
<b>Logistics</b>	$\beta_{PF,Li}$	Handling efficiency factor	EH <sub>L</sub>	Handler's expertise level for work item logistics	[0-2]
			ER <sub>L</sub>	Handler's experience rating for work item	[0-4]
			HD	Handling difficulty	[0-2]
	$K_{Li}^{WI}$	Logistics unit cost for work item (i)	$\mu$ L	Average unit cost for work item logistics	Value
<b>Assembly</b>	$\beta_{PF,Ai}$	Assembly efficiency factor	EI <sub>A</sub>	Installation process experience	[0-4]
			ER <sub>A</sub>	Assembler's expertise rating	[0-2]
			TC <sub>A</sub>	Type of connection used	[0-4]
	$\phi_{PF}^{Ai}$	Assembly constraints factor	SA <sub>A</sub>	Site accessibility	[0-2]
			ST <sub>A</sub>	Site storage allowance	[0-2]
$K_{Ai}^{WI}$	Assembly unit cost for work item (i)	$\mu$ A	Average unit cost for assembling work item	Value	
<b>Operation</b>	$\lambda_{PF}$	Useful life efficiency	M <sub>O</sub>	Maintainability of work item	[0-4]
			RM <sub>O</sub>	Removability of work item	[0-4]
			RU <sub>O</sub>	Reusability of work item	[0-4]
	Q <sub>WI</sub>	Quantity of work item			Value

452 Let OCA<sub>i</sub> represent a DFMA strategy such that  $0 \leq OCA_i \leq 1 (\forall i \in Z^+)$ , then the objective function Z is  
 453 expressed as;

$$Z = \max [\beta_{PF}, (1 - \phi_{PF}), \lambda_{PF}] \tag{1}$$

454 Where,  $\beta_{PF}$  = delivery efficiency factor,  $\phi_{PF}$  = delivery constraints factor,  $\lambda_{PF}$  = useful life efficiency  
 455 factor. These three factors are then used to determine the Total Factored Cost (TFC) for work items “WI”  
 456 for each of the design options and is expressed as;

$$TFC = \sum_1^n \frac{1}{\lambda_{PFi}} \left( \frac{\phi_{PF}^{Di}}{\beta_{PF,Di}} \cdot K_{Di}^{WI} + \frac{\phi_{PF}^{Mi}}{\beta_{PF,Mi}} \cdot K_{Mi}^{WI} + \frac{\phi_{PF}^{Li}}{\beta_{PF,Li}} \cdot K_{Li}^{WI} + \frac{\phi_{PF}^{Ai}}{\beta_{PF,Ai}} \cdot K_{Ai}^{WI} \right) \tag{2}$$

458 There are 13 sets of decision categories, which contain 29 decision variables for selecting a DFMA strategy  
 459 using datasets from BIM components and offsite construction stakeholder's external database. The three  
 460 sets of decision variables for the design category viz: (i) design delivery efficiency factor " $\beta_{PF,Di}$ "; (ii)  
 461 design constraints factor " $\phi_{PF}^{Di}$ "; and (iii) design unit cost for work items " $K_{Di}^{WI}$ " are expressed in Equation  
 462 3, 4 and 5 as;

$$\beta_{PF,Di} = 0.25 ER_D + 0.125 EL_D \quad (3)$$

$$\phi_{PF}^{Di} = 0.125 C_D + 0.125 DD_{WI} \quad (4)$$

$$K_{Di}^{WI} = Q_{WI} * \mu_D \quad (5)$$

463 The three sets of variables for the manufacturing category including: (i) production efficiency factor  
 464 " $\beta_{PF,Mi}$ "; (ii) production constraints factor " $\phi_{PF}^{Mi}$ ", and; (iii) manufacture unit cost for work item " $K_{Mi}^{WI}$ " are  
 465 expressed in Equation 6, 7 and 8.

$$\beta_{PF,Mi} = \frac{1}{3} (0.25 EX_M + 0.25 EM_M + 0.5 S_{PM}) \quad (6)$$

$$\phi_{PF}^{Mi} = (0.25 SR_M + 0.25 FP) \quad (7)$$

$$K_{Mi}^{WI} = Q_{WI} * \mu_M \quad (8)$$

466 The three sets of variables for the logistics category, which include handling efficiency factor " $\beta_{PF,Li}$ ",  
 467 logistics constraints factor " $\phi_{PF}^{Li}$ " and logistics unit cost for work item (i) " $K_{Li}^{WI}$ " are expressed in Equation  
 468 9, 10 and 11.

$$\beta_{PF,Li} = 0.25 EH_L + 0.125 ER_L \quad (9)$$

$$\phi_{PF}^{Li} = \frac{1}{2} (HD) \quad (10)$$

$$K_{Li}^{WI} = Q_{WI} * \mu_L \quad (11)$$

469 In the assembly category, the sets of variables for assessing DFMA options including: (i) assembly  
 470 efficiency factor " $\beta_{PF,Ai}$ "; (ii) logistics constraints factor " $\phi_{PF}^{Li}$ ", and; (iii) logistics unit cost for work item  
 471 " $K_{Li}^{WI}$ " are expressed in Equation 9, 10 and 11.

$$\beta_{PF,Ai} = \frac{1}{3} (0.25 EI_A + 0.5 ER_A + 0.25 TC_A) \quad (12)$$

$$\phi_{PF}^{Ai} = (0.25 SA_A + 0.25 ST_A) \quad (13)$$

$$K_{Ai}^{WI} = Q_{wi} * \mu A \quad (14)$$

472 Finally, the set of variables related to whole-life value of the work items i.e., useful life efficiency “ $\lambda_{PF}$ ” is  
473 expressed as;

$$\lambda_{PF} = \frac{1}{3} (0.25 M_o + 0.25 R M_o + 0.25 R U_o) \quad (15)$$

#### 474 4.2 Assessment of BIM-Model for Offsite Approach

475 Three construction methods viz traditional construction, prefabricated components, and volumetric  
476 construction were identified as the options for assessing the construction method for the BIM model. Tables  
477 5 – 7 show the three options of BIM object classification for offsite construction. One of the options reflects  
478 the traditional approach of quantity take-off to enable the comparison of offsite construction with traditional  
479 construction. Table 5 shows the quantity take-off for the tradition approach option.

480 *Table 5: Object Classification for DFMA Option-A (Traditional Construction)*

Global ID	Categories	Description	Unit	Quantity	Number of BIM objects
Trd02T55W13	Wall	Basic wall	m <sup>2</sup>	222.96	16
Trd03T14N04	Window	Fixed window (36” x 48”)	nr	12	12
Trd05T02D62	Door	Single-flush wooden door (36” x 84”)	nr	5	5
Trd01T12F17	Floor	Concrete slab (6”)	m <sup>2</sup>	111.48	10
					43

481 Table 6 shows the second option, which is the use of standardised prefabricated components. The  
482 components type is stored in the Big-DOR repository with a global Id among offsite construction peers and  
483 can be accessed and reused for BIM model design.

484 *Table 6: Object Classification DFMA Option-B (Components Prefabrication)*

Global_ID	Categories	Description	Unit	Quantity	Number of BIM objects
CompX15T346B	Façade component Type 346B	Wall panel (8”) with Single-flush wooden door (36” x 84”) and Fixed window (36” x 48”)	Nr	5	15
CompX15T357C	Façade component Type 357C	Wall panel (8”) with Fixed window (36” x 48”)	Nr	5	10
CompX15T357F	Façade component Type 357F	Wall panel (8”) with Fixed window (36” x 48”)	Nr	2	4
CompX15T338D	Façade component Type 338D	Wall panel (8”)	Nr	4	4
CompF32T267E	Concrete precast floor slab Type 267E	Concrete precast floor slab (6”)	Nr	5	5
CompF32T267B	Concrete precast floor slab Type 267B	Concrete precast floor slab (6”)	Nr	5	5
					43

485 Table 7 shows the third construction option, which is another approach to offsite construction and involves  
 486 the offsite prefabrication of volumetric modules rather than components. The standardised modules are  
 487 stored in the repository and can be reused.

488 **Table 7: Object Classification DFMA Option-C (Volumetric construction)**

Global_ID	Categories	Description	Unit	Quantity	Number of BIM objects
ModX89T12D	Volumetric module G12	Prefabricated prefinished volumetric concrete unit	GFA (m2)	22.3	10
ModX73T16K	Volumetric module G23	Prefabricated prefinished volumetric concrete unit	GFA (m2)	22.3	8
ModX73T16K	Volumetric module G34	Prefabricated prefinished volumetric concrete unit	GFA (m2)	22.3	8
ModX73T16K	Volumetric module G45	Prefabricated prefinished volumetric concrete unit	GFA (m2)	22.3	8
ModX89T12E	Volumetric module G56	Prefabricated prefinished volumetric concrete unit	GFA (m2)	22.3	9
					43

489 **4.3 Offsite Construction Options Quotation**

490 After identifying the candidate-products for the offsite construction options, conjunctive queries can now  
 491 be made to get unit costs for the candidate-products for the BIM model. Table 8 shows a sample of the  
 492 query response report for a BIM model assessment for method selection and suppliers' selection. The unit  
 493 costs are split into design cost, manufacture cost, logistics cost and assembly cost [71]. The various unit  
 494 costs are laid out according to the offsite construction phases as well as the query response from the  
 495 respective databases of offsite construction peers or suppliers.

496 **Table 8: Unit cost quotation by offsite construction peers for work items for each option**

Global_ID	Unit	Design Unit Cost by Peers		Manufacture Unit Cost by Peers		Logistics Unit Cost by Peers		Assembly Unit Cost by Peers	
		Designer-A	Designer-B	Manufacturer-A	Manufacturer-B	Logistics-A	Logistics-B	Assembler-A	Assembler-B
<b>Option-A</b>									
Trd02T55W13	m <sup>2</sup>	£6.50	£3.70	£55.00	£65.00	£32.50	£27.50	£145.00	£150.60
Trd03T14N04	nr	£97.00	£127.00	£2,140.00	£2,120.00	£414.00	£395.00	£950.00	£930.50
Trd05T02D62	nr	£93.00	£115.50	£750.00	£820.00	£175.00	£182.00	£670.00	£655.00
Trd01T12F17	m <sup>2</sup>	£6.50	£4.50	£110.00	£115.00	£311.00	£320.50	£196.50	£155.00
<b>Option-B</b>									
CompX15T346B	nr	£155.00	£120.00	£2,750.00	£2,420.00	£675.00	£642.00	£1,355.00	£2,725.00
CompX15T357C	nr	£140.00	£155.00	£2,500.00	£2,560.00	£650.00	£656.00	£1,550.00	£2,560.00
CompX15T357F	nr	£196.00	£114.50	£2,600.00	£2,400.00	£660.00	£640.00	£1,600.00	£2,500.00
CompX15T338D	nr	£192.00	£125.00	£2,700.00	£2,500.00	£670.00	£650.00	£1,475.00	£2,675.00
CompF32T267E	nr	£140.00	£110.00	£3,150.00	£4,950.00	£915.00	£895.00	£1,560.50	£2,785.50
CompF32T267B	nr	£150.00	£130.00	£5,250.00	£5,150.00	£725.00	£715.00	£1,550.50	£2,250.50
<b>Option-C</b>									
ModX89T12D	GFA	£145.00	£165.45	£850.00	£625.50	£220.00	£270.00	£149.00	£124.00
ModX73T16K	GFA	£140.00	£160.45	£850.00	£625.50	£220.00	£270.00	£149.00	£124.00

ModX73T16K	GFA	£145.00	£160.45	£850.00	£625.50	£220.00	£270.00	£149.00	£124.00
ModX73T16K	GFA	£145.00	£160.45	£850.00	£625.50	£220.00	£270.00	£149.00	£124.00
ModX89T12E	GFA	£150.00	£165.45	£850.00	£625.50	£220.00	£270.00	£149.00	£124.00

497 Other relevant information for assessing the proposed options include the user-based rating of the  
498 participating offsite construction suppliers, the evaluation of the prefabricated products for potential  
499 constraints and evaluation of factory and site conditions.

#### 500 4.4 Offsite Construction Suppliers Assessment

501 The optimisation algorithm integrates a supplier competency assessment, which extends suppliers  
502 assessment beyond quantitative parameters such as unit cost and distance to project site, and allows users  
503 to compare various peers or suppliers based on experience and expertise. The offsite construction peers’  
504 ratings according to their experience and expertise for the three options are shown in Table 9. In practice,  
505 the rating will be determined through established relationships with the OC peers or through a  
506 predetermined evaluation matrix.

507 *Table 9: User-based Ratings of OC Suppliers based on Expertise and Experience*

Offsite Construction Suppliers	Option A (Traditional)		Option B (Prefab Components)		Option C (Modular)	
	Experience [0-4]	Expertise [0-2]	Experience [0-4]	Expertise [0-2]	Experience [0-4]	Expertise [0-2]
Designer X	3	2	3	1	2	1
Designer Y	4	2	4	2	1	2
Manufacturer X	1	0	3	2	4	2
Manufacturer Y	2	1	4	2	2	1
Logistics X	4	2	3	1	3	1
Logistics Y	2	2	4	2	3	2
Assembler X	4	2	3	2	3	1
Assembler Y	2	1	4	2	3	2

#### 508 4.5 Offsite Construction Products Assessment

509 Offsite construction products were assessed in terms of the workability at various phases of offsite  
510 construction delivery. Such assessment would be user-based as most construction companies have a rating  
511 system for the ease of use for various construction elements. In practice, the Big-DOR will automatically  
512 calculate the respective ratings for offsite prefabricated products based on performance records obtained  
513 from offsite construction peers and suppliers. Table 10 shows a sample of a rating system for offsite  
514 construction products. These ratings were used in calculating the efficiency and constraints factors for the  
515 various options.

516 The repository-based assessment of work items or prefabricated products for various offsite construction  
517 strategies is essential for understanding and comparing the potential constraints for delivering the BIM  
518 design using the various options [72]. Inefficiencies can be mitigated by factors such as the expertise and  
519 experience possessed by the various offsite construction peers, as shown in Table 9, the user-based rating  
520 for offsite construction peers was integrated with the repository-based prefabricated products ratings to  
521 determine the efficiency penalty factors and the constraints penalty factors.

522 *Table 10: Repository-based Rating for Work Items for the OC Options*

Categories		Design complexity [0-4]	Detailing difficulty [0-4]	Standard parts [0-2]	Setup requirement [0-2]	Fragility of parts [0-2]	Handling difficulty [0-2]	Type of connection [0-4]	Site access requirement [0-2]	Site storage requirement [0-2]	Maintainability [0-4]	Removability [0-4]	Reusability [0-4]
<b>Option-A</b>													
Trd02T55W13	Wall	0	1	2	1	0	2	4	1	3	3	0	0
Trd03T14N04	Window	1	1	2	1	1	1	1	0	2	3	1	1
Trd05T02D62	Door	0	1	2	1	1	1	3	0	2	3	1	3
Trd01T12F17	Floor	0	1	2	1	0	2	4	1	3	3	0	0
<b>Option-B</b>													
CompX15T346B	Façade component Type 346B	2	2	2	2	1	2	3	1	1	3	2	3
CompX15T357C	Façade component Type 357C	2	2	2	2	1	2	3	1	1	3	2	3
CompX15T357F	Façade component Type 357F	2	2	2	2	1	2	3	1	1	3	2	3
CompX15T338D	Façade component Type 338D	2	2	2	2	1	2	3	1	1	3	2	3
CompF32T267E	Precast floor slab Type 267E	1	1	2	1	0	1	3	1	1	3	2	3
CompF32T267B	Precast floor slab Type 267B	1	1	2	1	0	1	3	1	1	3	2	3
<b>Option-C</b>													
ModX89T12D	Volumetric module G12	3	2	1	2	2	2	1	2	0	3	3	3
ModX73T16K	Volumetric module G23	3	2	1	2	2	2	1	2	0	3	3	3
ModX73T16K	Volumetric module G34	3	2	1	2	2	2	1	2	0	3	3	3
ModX73T16K	Volumetric module G45	3	2	1	2	2	2	1	2	0	3	3	3
ModX89T12E	Volumetric module G56	3	2	1	2	2	2	1	2	0	3	3	3

523

*Table 11: Efficiency and Constraints Factors for the Peers for each DFMA Option*


Global_ID	Designer A		Designer B		Manufacturer A		Manufacturer B		Logistics A		Logistics B		Assembler A		Assembler A		Useful Life Efficiency Factor
	Design delivery efficiency factor	Design constraints factor	Design delivery efficiency factor	Design constraints factor	Production efficiency factor	Production constraints factor	Production efficiency factor	Production constraints factor	Handling the efficiency factor	Logistics constraints factor	Handling the efficiency factor	Logistics constraints factor	Assembly Efficiency Factor	Assembly Constraints Factor	Assembly Efficiency Factor	Assembly Constraints Factor	
<b>Option-A</b>																	
Trd02T55W13	0.875	0.125	1.000	0.125	0.750	0.250	0.917	0.250	1.000	2.000	0.750	2.000	1.000	1.000	0.667	1.000	0.250
Trd03T14N04	0.875	0.250	1.000	0.250	0.583	0.500	0.750	0.500	1.000	0.500	0.750	0.500	0.750	0.500	0.417	0.500	0.417
Trd05T02D62	0.875	0.125	1.000	0.125	0.583	0.500	0.750	0.500	1.000	0.500	0.750	0.500	0.917	0.500	0.583	0.500	0.583
Trd01T12F17	0.875	0.125	1.000	0.125	0.750	0.250	0.917	0.250	1.000	2.000	0.750	2.000	1.000	1.000	0.667	1.000	0.250
<b>Option-B</b>																	
CompX15T346B	0.625	0.500	1.000	0.500	0.750	0.750	0.833	0.750	0.625	1.000	1.000	1.000	0.917	0.500	0.583	0.500	0.667
CompX15T357C	0.625	0.500	1.000	0.500	0.750	0.750	0.833	0.750	0.625	1.000	1.000	1.000	0.917	0.500	0.583	0.500	0.667
CompX15T357F	0.625	0.500	1.000	0.500	0.750	0.750	0.833	0.750	0.625	1.000	1.000	1.000	0.917	0.500	0.583	0.500	0.667
CompX15T338D	0.625	0.500	1.000	0.500	0.750	0.750	0.833	0.750	0.625	1.000	1.000	1.000	0.917	0.500	0.583	0.500	0.667
CompF32T267E	0.625	0.250	1.000	0.250	0.750	0.250	0.833	0.250	0.625	0.500	1.000	0.500	0.917	0.500	0.583	0.500	0.667
CompF32T267B	0.625	0.250	1.000	0.250	0.750	0.250	0.833	0.250	0.625	0.500	1.000	0.500	0.917	0.500	0.583	0.500	0.667
<b>Option-C</b>																	
ModX89T12D	0.500	0.625	0.625	0.625	0.667	1.000	0.417	1.000	0.625	1.000	0.875	1.000	0.750	0.500	0.333	0.500	0.750
ModX73T16K	0.500	0.625	0.625	0.625	0.667	1.000	0.417	1.000	0.625	1.000	0.875	1.000	0.750	0.500	0.417	0.500	0.750
ModX73T16K	0.500	0.625	0.625	0.625	0.667	1.000	0.417	1.000	0.625	1.000	0.875	1.000	0.750	0.500	0.417	0.500	0.750
ModX73T16K	0.500	0.625	0.625	0.625	0.667	1.000	0.417	1.000	0.625	1.000	0.875	1.000	0.750	0.500	0.417	0.500	0.750
ModX89T12E	0.500	0.625	0.625	0.625	0.667	1.000	0.417	1.000	0.625	1.000	0.875	1.000	0.750	0.500	0.417	0.500	0.750

524 **5 Results and Discussion**

525 This study involved the combination of suppliers’ ratings of experience and expertise with the constraints  
 526 involved in delivering various methods of offsite construction. As per Mahamadu et al. [73], expertise and  
 527 experience are important factors in demonstrating competence for BIM qualification during suppliers’  
 528 selection. The optimisation of offsite construction involves the estimation of the potential value accruable  
 529 from exploiting opportunities and mitigating risks [16]. In figure 6, the comparative rating of the potential  
 530 offsite construction peers is shown. The rating is based on the existing record of the suppliers based on their  
 531 levels of experience and competencies in relation to the delivery of various methods of offsite construction.  
 532 The consideration of these ratings in the optimisation algorithm will enable us to demonstrate the  
 533 consideration of value during the selection of DFMA options and the suppliers.

534 Through the assessment rating, the optimisation algorithm was used to estimate the cost implications of the  
 535 supplier’s level of expertise and experience on the delivery of the DFMA options. It was found that an  
 536 approach to quantitatively assess the experience and performance of the offsite construction peers and  
 537 supply chain is essential for understanding offsite maturity and developing delivery strategies for DFMA.

538 In Figure 6, the scores of the potential peers are shown for the respective DFMA options. It means that  
 539 peers can be assessed and monitored in terms of the performance growth for various offsite delivery  
 540 strategies. For example, the detailed design unit cost quoted by designer-Y (£165.45) for option C modules  
 541 was higher than designer-X (£145.00). However, the level of expertise of designer-X for Option C is also  
 542 higher than designer-Y. The scale for the experience [0-4] range includes not-experienced (0), slightly-  
 543 experienced (1), moderately-experienced (2), experienced (3), highly-experienced (4). While the scale for  
 544 the expertise [0-2] includes non-expert (0), average (1), and expert (2).



545

546

*Figure 6: Overview of peers’ competencies for the considered DFMA Option*



547 **5.1 Comparison of DFMA Options and Peers Using Total Cost**

548 While considering the constraints of delivering the various DFMA options, the experience and expertise of  
 549 the potential peers were also used to calculate the efficiency penalty factors for the options [5].  
 550 Consequently, the balance between the constraints and efficiency is a major determining factor for choosing  
 551 the DFMA option and peers.

552 *Table 12: Total Costs for DFMA Options according to Peers Quotation*

DFMA Options	Designer-X	Designer-Y	Manufacturer-X	Manufacturer-Y	Logistics-X	Logistics-Y	Assembly-X	Assembly-Y
Option-A	£3,802.86	<b>£3,651.07</b>	<b>£53,955.60</b>	£56,852.60	£47,759.48	<b>£47,510.74</b>	£68,985.02	<b>£65,298.18</b>
Option-B	£4,085.00	<b>£3,304.00</b>	<b>£84,250.00</b>	£90,200.00	£18,825.00	<b>£18,420.00</b>	<b>£39,180.00</b>	£67,305.00
Option-C	<b>£16,167.50</b>	£18,113.18	£94,775.00	<b>£69,743.25</b>	<b>£24,530.00</b>	£30,105.00	£16,613.50	<b>£13,826.00</b>

553 A preliminary assessment of the optimal DFMA option as well as the peer’s combination for delivering the  
 554 option can be seen in Table 13. Option-C appears to be the best option with a grand total cost of £124,266.75  
 555 as compared to Option-A (£170,415.59) and Option-B (£145,154.00). Also, the best combination of peers  
 556 for each DFMA option to achieve the lowest possible grand total cost also resulted in the combination of  
 557 designer-X, manufacturer-Y, logistics-X and assembler-Y for the delivery of option-C.

558 *Table 13: Peers combination for Delivery for DFMA Options*

Option-A	Peer combination	Designer-Y	Manufacturer-X	Logistics-Y	Assembler-Y	
	Total cost	£3,651.07	£53,955.60	£47,510.74	£65,298.18	<b>£170,415.59</b>
Option-B	Peer combination	Designer-Y	Manufacturer-X	Logistics-Y	Assembler-X	
	Total cost	£3,304.00	£84,250.00	£18,420.00	£39,180.00	<b>£145,154.00</b>
Option-C	Peer combination	Designer-X	Manufacturer-Y	Logistics-X	Assembler-Y	
	Total cost	£16,167.50	£69,743.25	£24,530.00	£13,826.00	<b>£124,266.75</b>

559 A significant limitation of using the peer quoted cost for selecting the DFMA option, and peers’  
 560 combination is that it fails to consider the efficiency and constraints penalty factors for delivering the  
 561 DFMA options by the peers. The next section shows the implementation of the proposed optimisation  
 562 algorithm to determine the total factored costs (TFC).

563 **5.2 Selection of DFMA Options and Peers Using Total Factored Cost**


564 Table 11 shows the efficiency and constraints penalty factors, which were applied to the total costs using  
 565 equation 2, to determine the cost implication of the suppliers’ performance as well as the constraints of  
 566 delivering the DFMA options.

567 *Table 14: Total Factored Costs for DFMA Options according to Peers*

DFMA Options	Designer-X	Designer-Y	Manufacturer-X	Manufacturer-Y	Logistics-X	Logistics-Y	Assembly-X	Assembly-Y
Option-A	£2,154.47	<b>£1,813.12</b>	£91,863.58	<b>£75,200.32</b>	<b>£342,077.65</b>	£455,184.08	<b>£238,360.22</b>	£342,181.81
Option-B	£4,032.40	<b>£2,028.20</b>	£84,391.88	<b>£76,335.27</b>	£35,343.53	<b>£21,594.66</b>	<b>£32,062.78</b>	£86,552.31
Option-C	£26,948.53	<b>£24,153.32</b>	<b>£189,587.92</b>	£223,223.04	£52,335.90	<b>£45,878.87</b>	<b>£14,770.51</b>	£23,232.33

568 In comparison to table 13, table 15 shows the optimal combination of peers for delivering each DFMA  
569 option. It is shown that the best option, according to the TFC, is Option-B as against Option-C in Table 13.  
570 This shows the significant impact of suppliers benchmarking and constraints assessment for DFMA options  
571 in decision making. Also, useful life efficiency, which considers the maintainability, removability, and  
572 reusability components was a major determining factor. This is evident from the comparison of the total  
573 cost for option-A (£170,415.59) and the total factored cost for option-A (£657,451.31). The optimal peers'  
574 combination for the best option, Option-B is to select designer-Y, manufacturer-Y, logistics-Y and  
575 assembler-Y.

576 In the history of construction, cost and time overrun have been persistent among other contributors to low  
577 productivity in construction [7]. The most common approach for generating construction cost estimates has  
578 been flawed over the years due to inaccuracies and the lack of consideration of essential factors such as  
579 expertise and experience of the process [2]. Figure 7 shows the comparison of the quoted costs by the  
580 suppliers with the factored cost obtained from the optimisation algorithm, which considered opportunities  
581 and constraints that influence project costs. This shows a huge potential impact for the Big-DOR system in  
582 improving construction practices through early supplier involvement; pricing rather than cost estimating;  
583 open-source data and standard specification, and; manufacturing-based construction [14].



584

585

*Figure 7: Comparison of Quoted Costs with Factored Costs*

586 The level of potential variation in cost can be assumed from the comparison of the quoted cost and the  
 587 factored cost. For example, the logistics cost for X can vary with up to 900% over the quoted cost due to  
 588 the level of experience and difficulty in handling such materials for the given method of construction.

589 **Table 15: Optimised Peers Combination for Delivery of DFMA Options**

Option-A	Peer combination	Designer-Y	Manufacturer-Y	Logistics-X	Assembler-X	
	Total cost	£1,813.12	£75,200.32	£342,077.65	£238,360.22	£657,451.31
Option-B	Peer combination	Designer-Y	Manufacturer-Y	Logistics-Y	Assembler-X	
	Total cost	£2,028.20	£76,335.27	£21,594.66	£32,062.78	£132,020.91
Option-C	Peer combination	Designer-Y	Manufacturer-X	Logistics-Y	Assembler-X	
	Total cost	£24,153.32	£189,587.92	£45,878.87	£14,770.51	£274,390.62

590 Over the last 20 years, the construction industry has only improved in productivity by 1%, which is far less  
 591 than the manufacturing industry that has increased its productivity by 1.7 times the construction industry.  
 592 Many stakeholders have proffered potential solutions for the improvement of productivity in the  
 593 construction industry. Some of the recommendations for productivity improvement include the adoption of  
 594 digital technologies in construction, adoption of offsite construction approaches and implementation of big  
 595 data-driven technologies for decision support, optimisation, and benchmarking.

### 596 5.3 Validation of the Proposed Big-DOR System

597 The proposed Big-DOR prototype was evaluated and validated through two focus group surveys and  
 598 discussion with experts in the construction industry. Two focus group discussions were held with a total  
 599 number of twelve participants. The participants were selected using expert sampling method with  
 600 predetermined selection criteria of a minimum of 2 years' experience in the construction industry and  
 601 knowledge of at least one of the following: BIM; DFMA; Big data, and; offsite construction. Table 16  
 602 shows the details of the focus group participants. The focus group participants comprised of 2 senior  
 603 architects, 4 senior structural engineers, 2 Quantity Surveyors (QS), 2 prefab suppliers, 1 construction  
 604 manager and 1 innovation director. Most of the participants (50%) had between 2 to 4 years of experience  
 605 while 16.6% had between 5 to 9 years, 16.6% had between 10 to 14 years, and 16.6% had over 15 years of  
 606 experience. All of the participants had knowledge of offsite construction, however, only 50% of them had  
 607 pre-existing knowledge of DFMA. 83.3% of the focus group participants had prior knowledge of BIM while  
 608 66.6% had knowledge of big data application in the construction industry.

609 **Table 16: Background of Focus Group Respondents**

		Frequency	Percentage (%)
Job description	Architect	2	16.6
	Structural Engineer	4	33.3
	Quantity Surveyor	2	16.6
	Construction Manager	1	8.3


	Prefab Supplier	2	16.6
	Construction Innovation Director	1	8.3
Years of Experience	2 – 4 years	6	50.0
	5 – 9 years	2	16.6
	10 -14 years	2	16.6
	Over 15 years	2	16.6
Expertise	BIM	10	83.3
	DFMA	6	50.0
	Big data	8	66.6
	Offsite construction	12	100.0

610 The focus group event involved three main steps, viz: (i) demonstration of the Big-DOR prototype; (ii)  
611 questionnaire evaluation of the prototype by focus group respondents, and; (iii) discussion about the merits,  
612 limitations and areas of improvement of the Big-DOR prototype. The participants were asked to evaluate  
613 the Big-DOR prototype based on three main criteria viz: applicability; ease of adoption and commercial  
614 acceptability. Table 17 shows the average rating of the proposed system as evaluated by the participants  
615 using a Likert scale of (1-5), with 1 being the lowest and 5 being the highest.

616 **Table 17: Average Rating of the Proposed System based on Validation Factors**

Factors	Question	Average Score (5)	Standard Deviation
Applicability	How applicable is the proposed Big-DOR system to your current line of business?	3.67	1.15
Ease of Adoption	In your opinion, how easy will it be for you to adopt the proposed system for your current operations?	2.75	0.62
Commercial Acceptability	How would you rate the commercial acceptability of the proposed system?	3.75	1.06

617 Figure 7 shows the evaluation summary of the proposed system by job description of the respondents. The  
618 participants were further asked to discuss about the proposed system in line with the pre-established  
619 validation factors. The outcome of the focus group discussion is presented below.



620

621

*Figure 7: Summary of Evaluation Results of the Proposed Big-DOR System*

622 **5.3.1 Applicability**

623 The expert participants discussed the practicability of adopting the proposed Big-DOR system as part of  
 624 the building design process. Two main demerits of the proposed Big-DOR system for the design process  
 625 that were identified including high design cost and increased design tasks. A structural designer opined that  
 626 “it is difficult to assess various opportunities offered by suppliers rather we have a specific go-to libraries  
 627 where we get products that we are familiar with” FG-1. It is clear that the success criteria considered by the  
 628 designers is mainly focused on design schedule, design budget, technical and functional specification [74].  
 629 However, from the perspective of the investment organisation, factors such as profitability, new product  
 630 line, technological capability and new market opportunities are very important [17]. The experts attributed  
 631 the merits of the proposed Big-DOR system to the clients’ market assessment and cost estimation process.  
 632 A QS confirmed the practicability of the system, saying “it would be interesting to pass on to the client and  
 633 contractor a list of suppliers with alternative products with cost and lead time information” FG-1. It was  
 634 resolved that despite the potential increase in design cost, which arise from comparing alternatives, there is  
 635 huge potential for significant decrease in cost of construction and an improvement in the efficiency of  
 636 successful delivery process of offsite construction [74].

637 **5.3.2 Ease of Adoption**

638 The focus group experts discussed about the potential most beneficial user groups for the proposed Big-  
 639 DOR system. The identified beneficial users include architects, suppliers, project managers, schedulers,  
 640 cost estimators and clients. A structural engineer suggested that the proposed system would be really  
 641 embraced by project planners due to the capability to pull important information about prefab object’s costs  
 642 and lead times, he opined that “this is an important plug for 5D BIM” FG-1. While considering the readiness  
 643 of prefab suppliers to use the proposed Big-DOR system, the prefab contractors considered the “increased  
 644 visibility” of their products to be a major driver. Theoretically, the increased visibility of prefab products

645 to potential clients/designers will translate to more sales and profitability for the suppliers. The experts  
646 further discussed the possibility of the proposed system to be used for a live web-based management of  
647 multiple stakeholders to deliver an offsite construction project [39]. While identifying the limitation of the  
648 proposed system to the easier adoption for repetitive buildings such as student housings and hospitals, an  
649 architect raised the question of the applicability of system for assessing design alternatives of prefab  
650 components by multiple suppliers for a BIM model for bespoke buildings. From the foregoing discussion,  
651 it is clear that the proposed system, although having its limitations, would enhance the design process for  
652 offsite construction by ensuring that functional requirements are met for both the individual prefab  
653 components and the whole integrated BIM model [21].

### 654 **5.3.3 Commercial Acceptability**

655 The expert participants resolved that the greatest commercial potential for the proposed Big-DOR system  
656 is to enable competitive bidding of prefab solutions for BIM models. An architect mentioned that “since  
657 the detailed specification of components would be coming from the prefab manufacturer, we just need to  
658 provide a wireframe BIM model and spatial requirement and then assess the prefab solutions offered by the  
659 suppliers” FG-2. The expert participants agreed that there is the need of intelligent information and  
660 knowledge management in the process of ensuring modular efficiency of prefab components as well as the  
661 integral performance of the components in the whole building system. While discussing the success of  
662 similar platforms that offer lesser functionalities, the experts argued that there is a huge potential for  
663 commercial adoption of the proposed Big-DOR system.

## 664 **6 Implication for Practice**

665 The practical implications of this study on various construction stakeholders and the construction industry  
666 are presented in this section. Firstly, with a view of transforming current practices, individuals in the  
667 construction industry such as construction managers and designers can adopt some of the aspects of the  
668 proposed framework to introduce the concepts of DFMA on their projects. For instance, a typical problem  
669 usually faced by designers in the construction industry is constant design changes according to changing  
670 methods of construction, which can be resolved by ensuring design flexibility. Also, construction managers  
671 with a transformational portfolio can leverage on Big-DOR to assess implementation choices during early-  
672 stage design. The illustrative case study demonstrated some critical information that should be considered  
673 in adopting the offsite construction approach.

674 The proposed framework is of immense importance to individuals seeking to propose new approaches as it  
675 provides adequate information for data integration and for identifying potential opportunities and barriers.  
676 From the perspectives of construction project teams seeking to adopt new methods of construction through  
677 integrated project delivery, an approach for collaborative delivery can be implemented through big data  
678 schema mediation in for a Win-Win optimisation strategy by understanding their complementary strengths  
679 and weaknesses in delivering offsite construction. Furthermore, there is a massive opportunity for  
680 construction process and product standardisation by identifying the variables that contribute most to the  
681 delivery cost and whole-life value.

682 This study has developed a framework that is capable of solving the age-long productivity challenge of the  
683 construction industry by providing a pathway to successful implementation. Consequently, construction

684 organisations can now clearly identify the factors which contribute to offsite construction adoption, which  
685 will then inform the implementation policies such as equipment procurement, training and development,  
686 digital skills acquisition and so on. Summarily, adopting a big data approach is central to the  
687 implementation of offsite construction in the industry, and as such, there is a need for improved data  
688 acquisition, sharing and integration with purely manufacturing-based companies. Also, the availability and  
689 pervasiveness of quality big data are necessary for optimisation algorithms to maximise the benefits of  
690 offsite construction adoption.

## 691 **7 Conclusion**

692 This study targeted to address the productivity lapses of the construction industry through the adoption of  
693 manufacturing approaches from the perspective of big data-driven BIM-based DFMA. A framework for  
694 developing a Big Data Design Options Repository for big data integration in early-stage design  
695 consideration was proposed. A significant contribution to knowledge in this study is the development of an  
696 extensible Big Data Design Options Repository, which allows the optimisation of building design based on  
697 design and construction factors such as resource availability, the expertise level of partners, constraints and  
698 whole-life cost efficiency. The repository has a practical implication for construction companies that intend  
699 to adopt new approaches in gauging their existing capabilities and the feasibility of implementing new  
700 methods from the design stage. The Big-DOR is an essential link between project planning database and  
701 practical DFMA strategies as well as their cost implication.

702 The Illustrative case study used in demonstrating the functionality of the system revealed that offsite  
703 construction requires a multi-objective optimisation approach, which allows designers to achieve the best  
704 prescriptive options in design development. This study has successfully integrated BIM, big data, DFMA and  
705 offsite construction in a single framework through the proposed Big-DOR system. The proposed system  
706 enables the early stage assessment of design alternatives for offsite construction by using big data from  
707 multiple suppliers' sources. The proposed Big-DOR system has a considerable potential to facilitate the  
708 adoption process of offsite construction, significantly improve the rate of adoption and expand the offsite  
709 construction market. Besides aiding in the selection of the most optimal choices and combination of design  
710 components, the proposed Big-DOR system also enable the selection of competent suppliers to deliver the  
711 optimal components.

712 A limitation of this study is the lack of adequate data sources because the offsite construction approach is  
713 still at its nascent stage in the UK construction industry. However, through this study, adequate data  
714 acquisition and BIM integration have been demonstrated to enhance the positive perspective of  
715 implementing offsite construction and adopting digital technologies [75]. Further research is recommended  
716 to ascertain the disposition of construction clients in adopting offsite construction through big data-driven  
717 digital technologies. In summary, the construction industry can benefit from adopting manufacturing  
718 approaches to attain similar productivity records with the manufacturing industry. Although, a significant  
719 barrier to adopting manufacturing approaches by construction clients include lack of adequate data to assess  
720 the manufacturing options. This study demystified the ambiguity between poor data practices and lack of  
721 offsite construction uptake and further established a growth cycle to enable continuous improvement  
722 between big data-driven approaches and offsite construction.

723 **Acknowledgement**

724 The authors will like to acknowledge the funding support for this study by the Engineering and Physical  
 725 Sciences Research Council (EPSRC), grant number EP/S031480/1. The authors will also like to appreciate  
 726 effort of Adekansola Labo-Popoola and Sofiat Abioye for facilitating the focus group discussion.

727 **References**

[1]	F. Barbosa, J. Woetzel, J. Mischke, M.J. Ribeirinho, M. Sridhar, M. Parsons, N. Bertram, S. Brown, Reinventing construction: a route to higher productivity. McKinsey Global Institute. (2017). Retrieved on March 1, 2019 from: <a href="https://www.mckinsey.com/~media/McKinsey/Industries/Capital%20Projects%20and%20Infrastructure/Our%20Insights/Reinventing%20construction%20through%20a%20productivity%20revolution/MGI-Reinventing-Construction-Executive-summary.ashx">https://www.mckinsey.com/~media/McKinsey/Industries/Capital%20Projects%20and%20Infrastructure/Our%20Insights/Reinventing%20construction%20through%20a%20productivity%20revolution/MGI-Reinventing-Construction-Executive-summary.ashx</a>
[2]	Infrastructure and Projects Authority, Transforming infrastructure performance. Open Government License. (2017), Retrieved on March 3, 2019 from: <a href="https://assets.publishing.service.gov.uk/government/uploads/system/uploads/attachment_data/file/664920/transforming_infrastructure_performance_web.pdf">https://assets.publishing.service.gov.uk/government/uploads/system/uploads/attachment_data/file/664920/transforming_infrastructure_performance_web.pdf</a>
[3]	R. F. Aziz, S. M. Hafez, Applying lean thinking in construction and performance improvement. Alexandria Engineering Journal 52 (4) (2013), pp. 679-695, <a href="https://doi.org/10.1016/j.aej.2013.04.008">https://doi.org/10.1016/j.aej.2013.04.008</a>
[4]	M. Bilal, L.O. Oyedele, J. Qadir, K. Munir, S.O. Ajayi, O.O. Akinade, H.A. Owolabi, H.A. Alaka, M. Pasha, Big data in the construction industry: a review of present status, opportunities, and future trends. Advanced Engineering Informatics, 30 (3) (2016), pp. 500-521. <a href="https://doi.org/10.1016/j.aei.2016.07.001">https://doi.org/10.1016/j.aei.2016.07.001</a>
[5]	A.Q. Gbadamosi, A.M. Mahamadu, L.O. Oyedele, O.O. Akinade, P. Manu, L. Mahdjoubi, C. Aigbavboa. Offsite construction: developing a BIM-based optimizer for assembly. Journal of Cleaner Production, 215 (2019), pp. 1180-1190. <a href="https://doi.org/10.1016/j.jclepro.2019.01.113">https://doi.org/10.1016/j.jclepro.2019.01.113</a>
[6]	KPMG. How offsite manufacturing can transform our industry. Smart Construction, 2016 Retrieved on March 1, 2019, from: <a href="https://assets.kpmg/content/dam/kpmg/pdf/2016/04/smart-construction-report-2016.pdf">https://assets.kpmg/content/dam/kpmg/pdf/2016/04/smart-construction-report-2016.pdf</a>
[7]	McKinsey Global Institute. Reinventing construction: a route to higher productivity. McKinsey and Company. (2017), Retrieved on March 3, 2019 from: <a href="https://www.mckinsey.com/~media/McKinsey/Industries/Capital%20Projects%20and%20Infrastructure/Our%20Insights/Reinventing%20construction%20through%20a%20productivity%20revolution/MGI-Reinventing-Construction-Executive-summary.ashx">https://www.mckinsey.com/~media/McKinsey/Industries/Capital%20Projects%20and%20Infrastructure/Our%20Insights/Reinventing%20construction%20through%20a%20productivity%20revolution/MGI-Reinventing-Construction-Executive-summary.ashx</a>
[8]	S. Azhar, Building information modeling (BIM): trends, benefits, risks, and challenges for the AECO industry. Leadership and Management in Engineering, 11 (3) (2011), pp. 241-252. <a href="https://doi.org/10.1061/(ASCE)LM.1943-5630.0000127">https://doi.org/10.1061/(ASCE)LM.1943-5630.0000127</a>
[9]	O.O. Akinade, L.O. Oyedele, M. Bilal, S.O. Ajayi, H.A. Owolabi, H.A. Alaka, S.A. Bello, Waste minimisation through deconstruction: a BIM based deconstructability assessment score (BIM-DAS). Resources, Conservation and Recycling, 105 (2015), pp. 167-176. <a href="https://doi.org/10.1016/j.resconrec.2015.10.018">https://doi.org/10.1016/j.resconrec.2015.10.018</a>
[10]	C. Eastman, P. Teicholz, R. Sacks, K. Liston, BIM handbook: a guide to building information modeling for owners, managers, designers, engineers and contractors. John Wiley and Sons. (2011) ISBN: 978-0-470-18528-5



[11]	B. Ilhan, H. Yaman, Green building assessment tool (GBAT) for integrated BIM-based design decisions. <i>Automation in Construction</i> , 70 (2016), pp. 26-37, <a href="https://doi.org/10.1016/j.autcon.2016.05.001">https://doi.org/10.1016/j.autcon.2016.05.001</a>
[12]	G. Boothroyd, P. Dewhurst, W. Knight, <i>Product design for manufacture and assembly</i> . Second ed. New York: Marcel Dekker. (1994) <a href="https://doi.org/10.1016/0010-4485(94)90082-5">https://doi.org/10.1016/0010-4485(94)90082-5</a>
[13]	S. Gao, R. Jin, W. Lu, Design for manufacture and assembly in construction: a review. <i>Building Research and Information</i> , (2019), pp. 1-13, <a href="https://doi.org/10.1080/09613218.2019.1660608">https://doi.org/10.1080/09613218.2019.1660608</a>
[14]	D. Mosey, <i>Early contractor involvement in building procurement: contracts, partnering and project management</i> . John Wiley & Sons. (2009) ISBN: 978-1-4051-9645-1
[15]	W. Pan, R. Sidwell, Demystifying the cost barriers to offsite construction in the UK. <i>Construction Management and Economics</i> , 29 (11) (2011), pp. 1081-1099. <a href="https://doi.org/10.1080/01446193.2011.637938">https://doi.org/10.1080/01446193.2011.637938</a>
[16]	A.Q. Gbadamosi, A.M. Mahamadu, P. Manu, O.O Akinade, F. Sierra, T.T. Lam, and A. Alzaatreh, A BIM based approach for optimization of construction and assembly through material selection. <i>Creative Construction Conference, 2018, CCC 2018, 30<sup>th</sup> June to 3<sup>rd</sup> July 2018, Ljubljana, Slovenia</i> . Retrieved on March 1, 2019 from: <a href="https://uwe-repository.worktribe.com/preview/865598/Creative%20Construction%20Conference%202018%20-%20Abdul%20et%20al%20BIM%20Paper%2013%204%2018%20-%20Copy%20-%20Copy%20Repository.pdf">https://uwe-repository.worktribe.com/preview/865598/Creative%20Construction%20Conference%202018%20-%20Abdul%20et%20al%20BIM%20Paper%2013%204%2018%20-%20Copy%20-%20Copy%20Repository.pdf</a>
[17]	F.H. Abanda, J.H.M Tah, F.K.T. Cheung, BIM in off-site manufacturing for buildings. <i>Journal of Building Engineering</i> , 14, (2017), pp. 89-102. <a href="https://doi.org/10.1016/j.jobee.2017.10.002">https://doi.org/10.1016/j.jobee.2017.10.002</a>
[18]	M. Lawson, R. Ogden, C. Goodier, <i>Design in modular construction</i> . CRC Press, Taylor and Francis. (2014), ISBN: 978-0-415-55450-3
[19]	V.W. Tam, I.W. Fung, M.C. Sing, and S.O. Ogunlana, 2015. Best practice of prefabrication implementation in the Hong Kong public and private sectors. <i>Journal of Cleaner Production</i> , 109, pp.216-231. <a href="https://doi.org/10.1016/j.jclepro.2014.09.045">https://doi.org/10.1016/j.jclepro.2014.09.045</a>
[20]	C.Z. Li, J. Hong, Xue, F., G.Q. Shen, X. Xu, L. Luo, SWOT analysis and Internet of Things-enabled platform for prefabrication housing production in Hong Kong. <i>Habitat International</i> , 57 (2016) 74-87, <a href="https://doi.org/10.1016/j.habitatint.2016.07.002">https://doi.org/10.1016/j.habitatint.2016.07.002</a>
[21]	Z. Yuan, C. Sun, Y. Wang, Design for Manufacture and Assembly-oriented parametric design for prefabricated buildings. <i>Automation in Construction</i> , 88 (2018), pp. 13-22. <a href="https://doi.org/10.1016/j.autcon.2017.12.021">https://doi.org/10.1016/j.autcon.2017.12.021</a>
[22]	T. Tan, W. Lu, G. Tan, F. Xue, K. Chen, J. Xu, J. Wang, S. Gao, Construction-Oriented Design for Manufacture and Assembly Guidelines. <i>Journal of Construction Engineering and Management</i> , 146 (8) (2020), p. 04020085. <a href="https://doi.org/10.1061/(ASCE)CO.1943-7862.0001877">https://doi.org/10.1061/(ASCE)CO.1943-7862.0001877</a>
[23]	P.S. Chinowsky, J.E. Meredith, Strategic management in construction. <i>Journal of Construction Engineering and Management</i> , 126 (1) (2000) 1-9. <a href="https://doi.org/10.1061/(ASCE)0733-9364(2000)126:1(1)">https://doi.org/10.1061/(ASCE)0733-9364(2000)126:1(1)</a>
[24]	Balfour Beatty. <i>Streamlined construction: Seven steps to offsite and modular building</i> . London: Balfour Beatty. (2018) Retrieved on March 1, 2019 from: <a href="https://www.balfourbeatty.com/media/317714/streamlined-construction-seven-steps-to-offsite-and-modular-building.pdf">https://www.balfourbeatty.com/media/317714/streamlined-construction-seven-steps-to-offsite-and-modular-building.pdf</a>
[25]	M. Arif, and C. Egbu, 2010. Making a case for offsite construction in China. <i>Engineering, Construction and Architectural Management</i> . ISSN: 0969-9988
[26]	C. Liu, F. Zhang, H. Zhang, Comparative analysis of off-site precast concrete and cast-in-place concrete in low-carbon built environment. <i>Fresenius Environmental Bulletin</i> , 29 (3) (2020), pp.1804-1812. <a href="https://www.researchgate.net/profile/Cong_Liu71/publication/340048807_Comparative_Analysi">https://www.researchgate.net/profile/Cong_Liu71/publication/340048807_Comparative_Analysi</a>

	<a href="https://doi.org/10.1016/j.autcon.2014.04.009">s_of Off-Site Precast Concrete and Cast-In-Place Concrete in Low-Carbon Built Environment/links/5e7427bd458515c677c63337/Comparative-Analysis-of-Off-Site-Precast-Concrete-and-Cast-In-Place-Concrete-in-Low-Carbon-Built-Environment.pdf</a>
[27]	L. Ding, Y. Zhou, B. Akinici. Building information modeling (BIM) application framework: the process of expanding from 3D to computable nD. <i>Automation in Construction</i> , 46 (2014), pp. 82-93, <a href="https://doi.org/10.1016/j.autcon.2014.04.009">https://doi.org/10.1016/j.autcon.2014.04.009</a>
[28]	Innovation, C.C., Adopting BIM for facilities management: solutions for managing the Sydney opera house. Cooperative Research Center for Construction Innovation, Brisbane, Australia. (2007)
[29]	R. Eadie, M. Browne, H. Odeyinka, C. McKeown, S. McNiff, BIM implementation throughout the UK construction project lifecycle: An analysis. <i>Automation in construction</i> , 36 (2013) pp.145-151. <a href="https://doi.org/10.1016/j.autcon.2013.09.001">https://doi.org/10.1016/j.autcon.2013.09.001</a>
[31]	F.J. Emmatty, S.P.Sarmah, Modular product development through platform-based design and DFMA. <i>Journal of Engineering Design</i> , 23 (9) (2012), pp.696-714. <a href="https://doi.org/10.1080/09544828.2011.653330">https://doi.org/10.1080/09544828.2011.653330</a>
[32]	S.O. Ajayi, L.O. Oyedele, Critical design factors for minimising waste in construction projects: a structural equation modelling approach. <i>Resources, Conservation and Recycling</i> , 137 (2018), pp.302-313. <a href="https://doi.org/10.1016/j.resconrec.2018.06.005">https://doi.org/10.1016/j.resconrec.2018.06.005</a>
[33]	L. Alvarez-Anton, M. Koob, J. Diaz, J. Minnert, Optimization of a hybrid tower for onshore wind turbines by building information modeling and prefabrication techniques. <i>Visualization in Engineering</i> , 4 (1) (2016), p.3. <a href="https://doi.org/10.1186/s40327-015-0032-4">https://doi.org/10.1186/s40327-015-0032-4</a>
[34]	H. Elnaas, K. Gidado, A.P. Philip, Factors and drivers effecting the decision of using off-site manufacturing (OSM) systems in house building industry. <i>Journal of Engineering, Project, and Production Management</i> , 4 (1) (2014), pp.51-58. <a href="http://www.ppml.url.tw/EPPM_Journal/volumns/04_01_January_2014/ID_062_4_1_51_58.pdf">http://www.ppml.url.tw/EPPM_Journal/volumns/04_01_January_2014/ID_062_4_1_51_58.pdf</a>
[35]	W. Pan, C. Goodier, House-building business models and off-site construction take-up. <i>Journal of architectural engineering</i> , 18 (2) (2012), pp.84-93. <a href="https://doi.org/10.1061/(ASCE)AE.1943-5568.0000058">https://doi.org/10.1061/(ASCE)AE.1943-5568.0000058</a>
[36]	N. Blismas, Off-site manufacture in Australia: current state and future directions. Cooperative Research Centre for Construction Innovation, (2007), ISBN: 978-0-9804262-8-1
[37]	V.K. Vernikos, C.I. Goodier, T.W. Broyd, P.C. Robery, A.G. Gibb, Building information modelling and its effect on off-site construction in UK civil engineering. <i>Proceedings of the Institution of Civil Engineers-Management, Procurement and Law</i> , 167 (3) (2014), pp.152-159. <a href="https://doi.org/10.1680/mpal.13.00031">https://doi.org/10.1680/mpal.13.00031</a>
[38]	X. Zhai, R. Reed, A. Mills, Factors impeding the offsite production of housing construction in China: an investigation of current practice. <i>Construction Management and Economics</i> , 32 (1-2) (2014), pp.40-52. <a href="https://doi.org/10.1080/01446193.2013.787491">https://doi.org/10.1080/01446193.2013.787491</a>
[39]	X. Yin, H. Liu, Y. Chen, M. Al-Hussein, Building information modelling for off-site construction: Review and future directions. <i>Automation in Construction</i> , 101 (2019), pp.72-91. <a href="https://doi.org/10.1016/j.autcon.2019.01.010">https://doi.org/10.1016/j.autcon.2019.01.010</a>
[40]	J. Schade, T. Olofsson, M. Schreyer, Decision-making in a model-based design process. <i>Construction Management and Economics</i> , 29 (4) (2011), pp.371-382. <a href="https://doi.org/10.1080/01446193.2011.552510">https://doi.org/10.1080/01446193.2011.552510</a>
[41]	D. Bryde, M. Broquetas, J.M. Volm, The project benefits of building information modelling (BIM). <i>International Journal of Project Management</i> , 31 (7) (2013), pp.971-980. <a href="https://doi.org/10.1016/j.ijproman.2012.12.001">https://doi.org/10.1016/j.ijproman.2012.12.001</a>

[42]	M. Kim, Q. Wang, J.C.P. Cheng, H. Sohn, C.C. Chang, Cloud-BIM based dimensional quality assessment of full-scale precast concrete elements. In EG-ICE (2014), European Group for Intelligent Computing in Engineering-21st International Workshop: Intelligent Computing in Engineering (2014), Retrieved on March 1, 2019 from: <a href="http://hdl.handle.net/1783.1/64454">http://hdl.handle.net/1783.1/64454</a>
[43]	H. Said, K. El-Rayes, Automated multi-objective construction logistics optimization system. Automation in Construction, 43 (2014), pp.110-122. <a href="https://doi.org/10.1016/j.autcon.2014.03.017">https://doi.org/10.1016/j.autcon.2014.03.017</a>
[44]	K.D. Wong, Q. Fan, Building information modelling (BIM) for sustainable building design. Facilities. (2013) DOI: 10.1108/02632771311299412
[45]	C. Zhang, T. Zayed, W. Hijazi, and Alkass, S., Quantitative assessment of building constructability using BIM and 4D simulation. Open journal of civil engineering, 6 (03) (2016), p.442. <a href="https://doi.org/10.4236/ojce.2016.63037">10.4236/ojce.2016.63037</a>
[46]	J.S. Goulding, F. Pour Rahimian, M. Arif, M.D. Sharp, New offsite production and business models in construction: priorities for the future research agenda. Architectural Engineering and Design Management, 11 (3) (2015), pp.163-184. <a href="https://doi.org/10.1080/17452007.2014.891501">https://doi.org/10.1080/17452007.2014.891501</a>
[47]	P.T. Lam, A.P. Chan, F.K. Wong, and F.W. Wong, Constructability rankings of construction systems based on the analytical hierarchy process. Journal of Architectural Engineering, 13 (1) (2007), pp.36-43. <a href="https://doi.org/10.1061/(ASCE)1076-0431(2007)13:1(36)">https://doi.org/10.1061/(ASCE)1076-0431(2007)13:1(36)</a>
[48]	M.R. Kannan, M.H. Santhi, Constructability assessment of climbing formwork systems using building information modeling. Procedia Engineering, 64 (2013), pp.1129-1138. <a href="https://doi.org/10.1016/j.proeng.2013.09.191">https://doi.org/10.1016/j.proeng.2013.09.191</a>
[49]	S. Martínez, A. Jardón, J.G. VÍtores, C. Balaguer, Flexible field factory for construction industry, Assembly Automation, 33 (2) (2013), pp.175-183. DOI: 10.1108/01445151311306708
[50]	M.K. Kim, S. McGovern, M. Belsky, C. Middleton, I. Brilakis, A suitability analysis of precast components for standardized bridge construction in the United Kingdom. Procedia Engineering, 164 (2016), pp.188-195. <a href="https://doi.org/10.1016/j.proeng.2016.11.609">https://doi.org/10.1016/j.proeng.2016.11.609</a>
[51]	B. Succar, Building information modelling framework: a research and delivery foundation for industry stakeholders. Automation in Construction, 18 (3) (2009), pp.357-375. <a href="https://doi.org/10.1016/j.autcon.2008.10.003">https://doi.org/10.1016/j.autcon.2008.10.003</a>
[52]	N. Thurairajah, D. Goucher, Advantages and challenges of using BIM: A cost consultant's perspective, In: 49th ASC Annual International Conference, 10th - 13th April 2013, San Luis Obispo, USA, (2013) <a href="http://ascpro.ascweb.org/chair/paper/CPRT114002013.pdf">http://ascpro.ascweb.org/chair/paper/CPRT114002013.pdf</a>
[53]	M. Machado, J. Underwood, A. Fleming, Implementing BIM to streamline a design, manufacture, and fitting workflow: a case study on a fit-out SME in the UK. International Journal of 3-D Information Modeling (IJ3DIM), 5 (3) (2016), pp.31-46. DOI: 10.4018/IJ3DIM.2016070103
[54]	F.H. Abanda, B. Kamsu-Foguem, J.H.M. Tah, BIM–new rules of measurement ontology for construction cost estimation. Engineering Science and Technology, an International Journal, 20 (2) (2017), pp.443-459. <a href="https://doi.org/10.1016/j.jestch.2017.01.007">https://doi.org/10.1016/j.jestch.2017.01.007</a>
[55]	C.Y. Chang, M.D. Tsai, Knowledge-based navigation system for building health diagnosis. Advanced Engineering Informatics, 27 (2) (2013), pp.246-260. <a href="https://doi.org/10.1016/j.aei.2012.12.003">https://doi.org/10.1016/j.aei.2012.12.003</a>
[56]	M. Das, J.C. Cheng, S. Shiv Kumar, BIMCloud: a distributed cloud-based social BIM framework for project collaboration. In Computing in Civil and Building Engineering (2014), pp. 41-48. <a href="https://doi.org/10.1061/9780784413616.006">https://doi.org/10.1061/9780784413616.006</a>

[57]	D.M. Salama, N.M. El-Gohary, Semantic text classification for supporting automated compliance checking in construction. <i>Journal of Computing in Civil Engineering</i> , 30 (1) (2016), p.04014106. <a href="https://doi.org/10.1061/(ASCE)CP.1943-5487.0000301">https://doi.org/10.1061/(ASCE)CP.1943-5487.0000301</a>
[58]	T. Mahfouz, J. Jones, A. Kandil, A machine learning approach for automated document classification: A comparison between SVM and LSA performances. <i>International Journal of Engineering Resource Innovation</i> , 2 (2) (2010), pp.53-62. <a href="http://refhub.elsevier.com/S1474-0346(16)30193-8/h0305">http://refhub.elsevier.com/S1474-0346(16)30193-8/h0305</a>
[59]	H.B. Liu, Y.B. Jiao, Application of genetic algorithm-support vector machine (GA-SVM) for damage identification of bridge. <i>International Journal of Computational Intelligence and Applications</i> , 10 (04) (2011), pp.383-397. DOI: 10.1142/S1469026811003215
[60]	Y.J. Chen, C.W. Feng, Y.R. Wang, H.M. Wu, Using BIM model and genetic algorithms to optimize the crew assignment for construction project planning. <i>International Journal of Technology</i> , 2 (3) (2011), pp.179-188. ISSN 2086-9614
[61]	K. Chen, W. Lu, Design for manufacture and assembly-oriented design approach to a curtain wall system: a case study of a commercial building in Wuhan, China. <i>Sustainability</i> , 10 (7) (2018), p.2211. <a href="https://doi.org/10.3390/su10072211">https://doi.org/10.3390/su10072211</a>
[62]	BCA, BIM design for design for manufacturing and assembly essential guide, Singapore: Building and Construction Authority. (2016). Retrieved on March 1, 2019 from: <a href="https://www.corenet.gov.sg/media/2032999/bim_essential_guide_dfma.pdf">https://www.corenet.gov.sg/media/2032999/bim_essential_guide_dfma.pdf</a>
[63]	C.Z. Li, F. Xue, X. Li, J. Hong, G.Q. Shen, An internet of things-enabled BIM platform for on-site assembly services in prefabricated construction. <i>Automation in Construction</i> , 89 (2018), pp.146-161. <a href="https://doi.org/10.1016/j.autcon.2018.01.001">https://doi.org/10.1016/j.autcon.2018.01.001</a>
[64]	R. Sacks, C. Eastman, G. Lee, P. Teicholz, BIM handbook: a guide to building information modeling for owners, designers, engineers, contractors, and facility managers. John Wiley & Sons. (2018) ISBN: 978-1-1182-87544
[65]	L. Ma, R. Sacks, U. Kattel, T. Bloch, 3D object classification using geometric features and pairwise relationships. <i>Computer-Aided Civil and Infrastructure Engineering</i> , 33 (2) (2018), pp.152-164. <a href="https://doi.org/10.1111/mice.12336">https://doi.org/10.1111/mice.12336</a>
[66]	J. Choi, S.K. Park, H.Y. Kim, S. Hong, Behaviour of high-performance mortar and concrete connections in precast concrete elements: experimental investigation under static and cyclic loadings. <i>Engineering Structures</i> , 100 (2015), pp.633-644.
[67]	M. Bilal, L.O. Oyedele, O.O. Akinade, M.D. Delgado, L. Akanbi, A. Ajayi, M.S. Younis, Design optimisation using convex programming: towards waste-efficient building designs. <i>Journal of Building Engineering</i> . (2019). <a href="https://doi.org/10.1016/j.engstruct.2015.06.009">https://doi.org/10.1016/j.engstruct.2015.06.009</a>
[68]	M. Belsky, R. Sacks, I. Brilakis, Semantic enrichment for building information modeling. <i>Computer-Aided Civil and Infrastructure Engineering</i> , 31 (4) (2016), pp.261-274. <a href="https://doi.org/10.1111/mice.12128">https://doi.org/10.1111/mice.12128</a>
[68]	X. Chen, W.S. Lu, Scenarios for applying big data in boosting construction: a review. In <i>Proceedings of the 21st International Symposium on Advancement of Construction Management and Real Estate</i> , (2018) pp. 1299-1306. Springer, Singapore. <a href="https://doi.org/10.1007/978-981-10-6190-5_114">https://doi.org/10.1007/978-981-10-6190-5_114</a>
[69]	J. Pan, S. Chitta, D. Manocha, FCL: A general purpose library for collision and proximity queries. In <i>2012 IEEE International Conference on Robotics and Automation</i> , (2012), pp. 3859-3866. IEEE. <a href="https://doi.org/10.1109/ICRA.2012.6225337">https://doi.org/10.1109/ICRA.2012.6225337</a>

[70]	E.F. Begley, M.E. Palmer, K.A. Reed, Semantic mapping between IAI ifcXML and FIATECH AEX Models for centrifugal pumps. US Department of Commerce, National Institute of Standards and Technology. (2005). <a href="https://tsapps.nist.gov/publication/get_pdf.cfm?pub_id=100983">https://tsapps.nist.gov/publication/get_pdf.cfm?pub_id=100983</a>
[71]	R. Gerth, A. Boqvist, M. Bjelkemyr, B. Lindberg, Design for construction: utilizing production experiences in development. <i>Construction Management and Economics</i> , 31 (2) (2013), pp.135-150. <a href="https://doi.org/10.1080/01446193.2012.756142">https://doi.org/10.1080/01446193.2012.756142</a>
[72]	Z. Ma, Z. Liu, BIM-based intelligent acquisition of construction information for cost estimation of building projects. <i>Procedia Engineering</i> , 85 (2014), pp.358-367. <a href="https://www.researchgate.net/profile/Zhiliang_Ma/publication/271070338_BIM-based_Intelligent_Acquisition_of_Construction_Information_for_Cost_Estimation_of_Building_Projects/links/54bf6cbf0cf2f6bf4e04e942.pdf">https://www.researchgate.net/profile/Zhiliang_Ma/publication/271070338_BIM-based_Intelligent_Acquisition_of_Construction_Information_for_Cost_Estimation_of_Building_Projects/links/54bf6cbf0cf2f6bf4e04e942.pdf</a>
[73]	A.M. Mahamadu, L. Mahdjoubi, C.A. Booth, Critical BIM qualification criteria for construction pre-qualification and selection. <i>Architectural Engineering and Design Management</i> , 13 (5) (2017), pp.326-343. <a href="https://doi.org/10.1080/17452007.2017.1296812">https://doi.org/10.1080/17452007.2017.1296812</a>
[74]	O.A. Olawale, L.O. Oyedele, H.A. Owolabi, Construction practitioners' perception of key drivers of reputation in mega-construction projects. <i>Journal of Engineering, Design and Technology</i> (2020). DOI: 10.1108/JEDT-10-2019-0255
[75]	Y. Jung, M. Joo, Building information modelling (BIM) framework for practical implementation. <i>Automation in Construction</i> , 20 (2) (2011), pp.126-133. <a href="https://doi.org/10.1016/j.autcon.2010.09.010">https://doi.org/10.1016/j.autcon.2010.09.010</a>